UL/cUL SYSTEM NO. F-A-2156

PVC PLASTIC SHOWER DRAIN THROUGH CONCRETE FLOOR ASSEMBLY

F-RATING = 3-HR.

T-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW) FT-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW)

FH-RATING = 3-HR.

FTH-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW)

L-RATING AT AMBIENT = LESS THAN 1 CFM / SQ FT


L-RATING AT 400° F = LESS THAN 1 CFM / SQ FT

W-RATING = CLASS I

NOTE: TESTED WITH A 50 Pa PRESSURE DIFFERENTIAL

INSTALLATION PROCEDURE

CROSS-SECTIONAL VIEW





HILTI, Inc. Plano, Texas USA (800) 879-8000

Sheet	1 of 2
Scale	13/64" = 1"
Date	Mar. 22, 2023

FA 2156g

FA2156g.032223

UL/cUL SYSTEM NO. F-A-2156

PVC PLASTIC SHOWER DRAIN THROUGH CONCRETE FLOOR ASSEMBLY

F-RATING = 3-HR.

T-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW) FT-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW) FH-RATING = 3-HR.

FTH-RATING = 0-HR. OR 2-HR. (SEE NOTE NO. 1 BELOW) L-RATING AT AMBIENT = LESS THAN 1 CFM / SQ FT L-RATING AT 400° F = LESS THAN 1 CFM / SQ FT

W-RATING = CLASS I

NOTE: TESTED WITH A 50 Pa PRESSURE DIFFERENTIAL

- 1. LIGHTWEIGHT OR NORMAL WEIGHT CONCRETE FLOOR ASSEMBLY (MINIMUM 4-1/2" THICK) (3-HR. FIRE-RATING).
- 2. HILTI FIRESTOP DRAIN FLANGE CAST OR GROUTED IN CONCRETE FLOOR ASSEMBLY TO CONSIST OF ONE OF THE FOLLOWING:
 - A. HILTI CP 681 75/2" N TUB BOX FLANGE.
 - B. HILTI CP 681 SD-FD FIRESTOP DRAIN FLANGE (SEE NOTE NO. 2 BELOW).
- 3. NOMINAL 2" DIAMETER PVC PLASTIC DRAIN PIPE (SCHEDULE 40) (CELLULAR OR SOLID CORE) CEMENTED INTO HILTI FIRESTOP DRAIN FLANGE WITH PVC GLUE (PROVIDED BY OTHERS).
- 4. PVC PLASTIC SHOWER FITTING WITH CHROMED STEEL STRAINER (SIZED TO ACCOMMODATE PIPE) CEMENTED IN PVC DRAIN PIPE (PROVIDED BY OTHERS).
- 5. [OPTIONAL] NOMINAL 2" DIAMETER (MIN. 32 GA.) CORRUGATED STAINLESS STEEL SHIELDED RUBBER NO-HUB CONNECTOR.
- 6. [OPTIONAL] NOMINAL 2" DIAMETER CAST IRON PIPE AND P-TRAP SECURED TO PVC PIPE WITH NO-HUB COUPLER.
- 7. [OPTIONAL] HILTI CP 648E WRAP STRIP (NOMINAL 3/16" THICK x 1" WIDE) CONTINUOUSLY WRAPPED AROUND THE OUTER CIRCUMFERENCE OF THE PIPE, COVERING TWO TIMES, WITH ENDS BUTTED AND HELD IN PLACE WITH TAPE (SEE NOTE NO. 2 BELOW).
- 8. [OPTIONAL] HILTI 1" RETAINING COLLAR WRAPPED OVER WRAP STRIPS, OVERLAPPING MINIMUM 1" (SEE NOTE NO. 2 BELOW).
- 9. HILTI RETAINING COLLAR CLAMP FASTENED AT MID-HEIGHT OF RETAINING COLLAR, WHEN INSTALLED (SEE NOTE NO. 2 BELOW).
- 10. SECURE EVERY OTHER TAB OF RETAINING COLLAR, WHEN INSTALLED, TO CONCRETE FLOOR WITH 1/4" DIAMETER BY 1-1/4" LONG STEEL EXPANSION BOLTS, 1-1/4" LONG CONCRETE SCREW ANCHORS, 0.145" DIAMETER BY 1-1/4" LONG POWDER ACTUATED FASTENERS UTILIZING A 9/16" DIAMETER STEEL WASHER, HILTI 1/4" DIAMETER BY 1-1/4" LONG KWIK-CON II+ CONCRETE SCREW ANCHORS, HILTI 1/4" DIAMETER BY 1-3/4" LONG KWIK-BOLT 3 STEEL EXPANSION ANCHORS, OR HILTI X-DNI 27 P8 215 POWDER ACTUATED FASTENERS WITH INTEGRATED 9/16" DIAMETER STEEL WASHERS (SEE NOTE NO. 2 BELOW).

NOTES: 1. T-RATING IS 2-HR. WHEN HILTI CP 648E AND RETAINING COLLAR (ITEMS NO. 7 THROUGH 10) ARE INSTALLED. 2. WHEN HILTI CP 681 SD-FD FIRESTOP DRAIN FLANGE IS INSTALLED ITEMS NO. 7 THROUGH 10 ARE REQUIRED.



HILTI, Inc. Plano, Texas USA (800) 879-8000 Sheet 2 of 2 Scale Date Mar. 22, 2023

Drawing No. FA 2156a

Saving Lives through Innovation and Education