RESIDENTIA	I BUILDING		
	ate: Flat deck concrete slab		
SHEET	MEP PENETRATIONS THRU	SYSTEM	DESCRIPTION
		F-A-1016	METAL PIPE THROUGH CONCRETE FLOOR (2-HR)
	FLOORS	F-A-2053	PLASTIC PIPE THROUGH CONCRETE FLOOR (2-HR)
		F-A-2065	PLASTIC PIPE THROUGH CONCRETE FLOOR (2-HR)
4.1		F-A-2213	PLASTIC PIPE THROUGH CONCRETE FLOOR (2-HR)
		F-A-5015	METAL PIPE WITH AB/PVC INSULATION THROUGH CONCRETE FLOOR (2-HR)
		F-A-5017	METAL PIPE WITH GLASS FIBER INSULATION THROUGH CONCRETE FLOOR (2-HR)
		F-A-5046	METAL PIPE WITH AB/PVC OR GLASS FIBER INSULATION THROUGH CONCRETE FLOOR (2-HR)
		C-AJ-1226	METAL PIPE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-1513	MULTIPLE METAL PIPE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-2109	PLASTIC PIPE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-2167	PLASTIC PIPE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-3095	CABLE BUNDLE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-3283	CABLE BUNDLE THROUGH CONCRETE OR MASONRY (2-HR)
4.2	FLOORS OR WALLS	C-AJ-5090	METAL PIPE WITH AB/PVC INSULATION THROUGH CONCRETE OR MASONRY (2-HR)
7.2	I LOOKS OK WALLS	C-AJ-5091	METAL PIPE WITH GLASS FIBER OR CALCIUM SILICATE INSULATION THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-6042	ELECTRICAL BUSWAY THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-7051	METAL DUCT (WITHOUT DAMPER) THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-7084	ROUND SHEET METAL DUCT THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-7145	SHEET METAL DUCT WITH GLASS FIBER INSULATION THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-8099	MULTIPLE METAL PIPE THROUGH CONCRETE OR MASONRY (2-HR)
		C-AJ-8143	MULTIPLE PENETRATION THROUGH CONCRETE OR MASONRY (2-HR)
		W-L-1054	METAL PIPE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-1389	MULTIPLE METAL PIPE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-2078	PLASTIC PIPE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
	GYPSUM WALLS	W-L-2128	PLASTIC PIPE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-3334	CABLE BUNDLE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
4.3		W-L-3414	CABLE THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-5028	PLASTIC PIPE WITH AB/PVC INSULATION THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-5029	METAL PIPE WITH GLASS FIBER OR CALCIUM SILICATE INSULATION THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-7042	METAL DUCT (WITHOUT DAMPER) THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-7155	METAL DUCT THROUGH GYPSUM WALL ASSEMBLY (2-HR)
		W-L-7156 W-L-8079	METAL DUCT WITH GLASS FIBER INSULATION THROUGH GYPSUM WALL ASSEMBLY (2-HR)
4.4	CONCRETE OR MASONRY WALL	W-L-8079 W-J-3215	MULTIPLE PENETRATIONS THROUGH GYPSUM WALL ASSEMBLY (2-HR)  CABLE BUNDLE (<1") (2-HR)
4.4	MEMBRANE PENETRATION	CLIV or CLIV-76	MEMBRANE PENETRATION IN GYPSUM WALL ASSEMBLY (2-HR)
4.5	MEMBRANE FENETRATION	CLIV OI CLIV-70	WEWISTANCE FENETICATION IN GTF30W WALL ASSEMBLE (2-FIX)
	JOINTS	SYSTEM	DESCRIPTION
	301113	BW-S-0002	BOTTOM OF WALL JOINT (2-HR)
		BW-S-0039	BOTTOM OF WALL JOINT (2-HR)
4.6	GYPSUM WALL	HW-D-0106	TOP OF WALL JOINT (2-HK)
1.0	311 3311 777722	HW-D-0209	TOP OF WALL JOINT (2-HR)
		HW-D-0757	TOP OF WALL JOINT (2-HR)
		HW-D-0342	TOP OF WALL JOINT (2-HR)
4.7	GYPSUM SHAFT WALL	HW-D-0572	TOP OF WALL JOINT (2-HR)
4.8	GYPSUM CHASE WALL	HW-D-0758	TOP OF WALL JOINT: GYPSUM CHASE WALL ASSEMBLY (2-HR)
		HW-D-0268	TOP OF WALL JOINT: CONCRETE WALL OR BLOCK WALL ASSEMBLY (3-HR)
4.9	CONCRETE OR MASONRY WALLS	HW-D-0403	TOP OF WALL JOINT: CONCRETE WALL OR BLOCK WALL ASSEMBLY (3-HR)
		1	1

## **UL FIRE RESISTANCE DIRECTORY NOMENCLATURE**

Through Penetrations First letter represents what is Second letter(s) provide more information Example: CAJ1150 Four digit number describes the penetrating item(s) about the floor or wall: being penetrated C = FLOOR OR WALLPENETRATION F= FLOOR CONCRETE FLOORS WITH A MINIMUM 0000 - 0999 BLANK OPENINGS W = WALLS THICKNESS LESS THAN OR EQUAL TO 5 IN C = FLOORS OR WALLS (COMBINED) 1000-1999 METAL PIPE, CONDUIT OR TUBING CONCRETE FLOORS 5" OR LESS = CONCRETE FLOORS WITH A MINIMUM THICKNESS GREATER THAN 5 IN 2000 - 2999 NON METALLIC PIPE CONDUIT OR TUBING C = FRAMED FLOORS CONCRETE OR MASONRY WALLS 3000 - 3999 CABLES 4000 - 4999 CABLE TRAYS 8" OR LESS 1150 = METAL PIPE, CONDUIT OR TUBING = FOR-CEILING ASSEMBLIES CONSISTING 5000 - 5999 INSULATED PIPES OF CONCRETE WITH MEMBRANE 6000 - 6999 MISCELLANEOUS ELECTRICAL (BUSWAY) PROTECTION CONCRETE OR MASONRY WALLS WITH A 7000 - 7999 MISCELLANEOUS MECHANICAL 8000 - 8999 MIXED PENETRATING ITEMS MINIMUM THICKNESS LESS THAN OR **EQUAL TO 8 IN** 9000 - 9999 RESERVED FOR FUTURE USE = FRAMED WALLS

Joint Systems	T		
First letters identify the type of joint:	Second letter(s) provide more information about the floor or wall:	Four digit number describes the penetrating item(s)	Example: HWD0757
CJ = CONTINUITY HEAD OF WALL FF = FLOOR TO FLOOR	S NO MOVEMENT (STATIC)	0000 - 0999 LESS THAN OR EQUAL TO 2"	HW = HEAD TO WALL
VW = WALL TO WALL FW = FLOOR TO WALL HW = HEAD TO WALL	D = ALLOWS MOVEMENT (DYNAMIC)	1000-1999 GREATER THAN 2" AND LESS THAN OR EQUAL TO 6"	D = ALLOWS MOVEMENT (DYNAMIC)
BW = BOTTOM OF WALL		2000 - 2999 GREATER THAN 6" AND LESS THAN OR EQUAL TO 12	0757 = LESS THAN OR EQUAL TO 2"
		3000 - 3999 GREATER THAN 12" AND LESS THAN OR EQUAL TO 24"	
		4000 - 4999 GREATER THAN 24"	

Notes:

Refer to the following specifications for firestopping. a. 07 84 00 Firestopping b. 07 84 13 Penetration Firestopping c. 07 84 43 Joints Firestopping d. 22 00 00 Plumbing e. 23 00 00 HVAC f. 26 00 00 Electrical g. 27 05 37 Communication Systems

For Quality Control requirements, refer to the Quality Control portion of the specification.

the

- 2. Details shown are typical details. Always refer to the listed system detail for complete system requirements. If field conditions do not match requirements of details, approved alternate details shall be utilized. Design requirements, field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following: Fire Rating (F-Rating)
- Temperature Rating (T-Rating) Leakage Rating (L-Rating)
- Water Rating (W-Rating)
- Annular Space
- Percent Fill
- Type and thickness of fire-rated construction.
- If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.
- References:
- 2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.
- NFPA 101 Life Safety Code
- NFPA 70 National Electric Code
- All governing local and regional building codes.
- 5. Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of construction being penetrated.
- 6. All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information.
- Warning! Do Not Disturb Through Penetration Firestop
- UL System # \* Product(s) used Hourly Rating (F-Rating)
- Installation Date Contractor's Name
- 7. For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as

classified by Underwriter's Laboratories,

Current as of November 19, 2017. System details subject to change without notice.

Fire Resistance Directory (Volume 1).

SHEET NUMBER

4.0

JOB NUMBER: DRAWN:


S. S.


CHECKED:

**ISSUE DATE: 01-25-2018** 

**REVISIONS:** 

SHEET NAME: Index of Drawings





System No. F-A-1016

When metallic pipes of diameters smaller than those shown above are installed within the device, CP618 Firestop Putty Stick or mineral woo

Fill, Void or Cavity Material\* - Putty (Not Shown) — Min 1 in. (25 mm) thickness of fill material applied within annulus flush with top surface of

4A. Packing Material (Not Shown) — As an alternate to Item 4, min 4 in. (102 mm) thickness of min 4 pcf (64 kg/m3) mineral wool insulation firmly

4B. Firestop Device\* - Top Seal Plug — (Optional. Not Shown) - Top seal plug for use with CP 680-M 2" and CP 680-P 2" devices and nom pipe,

manufacturer's instructions. When top seal plug is used, no putty (Item 4) or packing material (Item 4A) is required. W Rating applies only to nom

, 1-1/4, 1-1/2 and 2 in. (25, 32, 38 and 51 mm) diam copper pipe/tube in conjunction with 2" CPS Top Seal and CP 680-M 2" or CP 680-P(X) 2"

System No. F-A-2213

conduit or tubing sizes of 1/2 in. (13 mm) to 2 in. (51 mm) diam. Plug is friction fit into top of firestop device (Item 2) in accordance with the

+ L Rating applies only to CP 680-M and -P(X) devices and only when the nom diam of pipe equals size of device (2 in. diam pipe in 2" device

Firestop Device

CP680N-75/2.5"or CP682-75/2.5'

P 680-M 2", CP 680-P 2, CP 680-PX

CP680N-75/2.5"or CP682-75/2.5"

P 680-M 2" CP 680-P 2" CP 680-PX

CP 680-M 3" CP 680-P 3" CP 680-PX

CP 680-M 4", CP 680-P 4"

CP680N-160/6"

CP 680-M 6". CP 680-P 6"

e firestop device and metallic penetrant shall be sized as follows

2-1/2 to 3 in. (64 to 76 mm)

insulation shall be installed within the device.

etc.) I Rating does not apply to CP 680N and CP682 devices

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 618 Firestop Putty Stick

packed to the fullest extent possible within annulus flush with top surface of device.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CPS Top Seal Plug

4 in. (102 mm)


6 in. (152 mm)

Nom Pipe Diam +. ++

to 2-1/2 in.(38 to 64 mm) - Other than copper pipe or tubing

2 to 2 in.(38 to 51 mm) - Other than copper pipe or tubing

to 2-1/2 in. (51 to 64 mm) - Copper pipe or tubing



Hilti Firestop Systems

31. Firestop Device\* - Water Barrier Module — (Optional, Not Shown) - Used as an alternate to the top seal plug (Item 4B) and in combination

Penetrant Type (See Item 3 above) Nom Penetrant Diam Size of Device/Module


with the CP 680-M and CP 680-P(X) devices to achieve a W Rating. Module is threaded onto top of device. See Table below for sizes of

device/module and penetrants covered. When water barrier module is used, a W Rating applies to the water barrier module, device and

ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada)

penetrant sizes specified in Table below. For W Rating with Water Barrier Module, pipe shall be installed from bottom of device.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — Water Barrier Module



Through Penetrants — One nonmetallic pipe or conduit to be installed within the firestop system. Pipe or conduit to be rigidly supported on

both sides of floor assembly. For W Rating with Water Barrier Module, pipe shall be installed from bottom of device. The following types and

A. Polyvinyl Chloride (PVC) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 solid or cellular core PVC pipe for use in closed

B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 6 in. (152 mm) diam (or smaller) SDR11 or SDR13.5 CPVC pipe for use in closed

C. Rigid Nonmetallic Conduit+ — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 PVC conduit installed in accordance with the National

+ L Rating applies only to CP 680-P(X) devices and only when the nom diam of pipe equals size of device (2 in, diam pipe in 2" device etc.)

Firestop Device\* — (Not shown) -Top Seal Plug for use with CP 680-P(X) 2" device Installed in accordance with the manufacturer's instructions

1-1/2 in. (38 mm). W Rating applies only to the IPS Top Seal Plug and nom 2 in. diam penetrants, and to CPS Top Seal Plugs with nom 1/2 to 2

4A. Firestop Device\* - Water Barrier Module — (Optional, Not Shown) - Used as an alternate to the top seal plug (Item 4). Applies to nom 2", 3", 4"

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

and 6" water barrier modules used in combination with the CP 680-P(X) 2", CP 680-P(X) 3", CP 680-P 4" CP 680-P 6" devices, respectively, and supplied by device manufacturer. Module is threaded onto top of device. W Rating applies only when water barrier module is used and nom diam

The Top Seal Plug is optional for nom 1-1/2 in. (38 mm) pipes and conduits. Top Seal Plugs are required for all pipes and conduits less than nom

CP 680-75/2.5"N

CP 680-110/4"N

CP 680-P 4

CP 680-160/6"N

CP 680-P 6"

P 680-P 2" CP 680-PX 2

CP 680-P 3" CP 680-PX :

(process or supply) or vented (drain, waste or vent) piping systems.

2 in. to 2 in. (19 mm to 51 mm)

in. to 4 in. (76 mm to 102 mm)

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CPS and IPS Top Seal Plugs

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — Water Barrier Module


(process or supply) piping systems.


Rating does not apply to CP 680N devices.

of penetrant equals size of device.

+Bearing the UL Listing Mark

Electrical Code (NFPA No. 70).





2B. Firestop Device\* — (Optional. Not shown) - Alternate to Water Barrier Module (Item 2A). Top Seal Plug for use with CP 680-P(X) 2" device Installed in accordance with the manufacturer's instructions. W Rating applies only to the IPS Top Seal Plug with nom 2 in. (51 mm) diam HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — IPS Top Seal Plugs Page: 1 of 2

CP 680-110/4" 4 in. (102 mm) CP 680-160/6"N L Rating applies only to CP 680-P(X) devices. L Rating applies only when the nom diam of pipe equals size of device (2 in. diam pipe in 2" \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), nderwriters Laboratories, Inc. June 29, 2015

Through Penetrants — One nonmetallic pipe or conduit to be installed within the firestop system. Pipe or conduit to be rigidly supported on

A. Acryonitrile Butadiene Styrene (ABS) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 cellular or solid core pipe for use in

and sizes of nonmetallic pipes or conduits may be used:

he firestop device and nonmetallic penetrant shall be sized as follows:

closed (process or supply) or vented (drain, waste or vent) piping systems.

1-1/2 in. to 2 in. (38 to 51 mm

both sides of floor-ceiling assembly. For W Rating with Water Barrier Module, pipe shall be installed from bottom of device. The following types  $\bot$ 

B. Fire Retardant Polypropylene (FFPP) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or

CP 680-75/2.5"N

Nom Pipe Diam, in. (mm)	Nom Pipe Covering Thickness, in. (mm)	Firestop Device	T Rating, Hr	
1/2 (13)	1 (25)	CP 680-75/2.5"N, CP 682-75/2.5"	2/4	
	1 (25)	CP 680-M 2", CP 680-P 2", CP 680-PX 2"	3/4	
1 (25)	1 (25)	CP 680-M 3", CP 680-P 3", CP 680-PX 3"	3/4	
1 (25) (See Item 5)	1 1/2 /20)	CP 682-110/4"	2/4	
1 (25) (See item 5)	1-1/2 (38)	CP 680-M 4", CP 680-P 4"	3/4	
2 (51)	1 (25)	CP 680-110/4"N, CP 682-110/4"		
2 (51)		CP 680-M 4", CP 680-P 4"	1	
0 (54)	0 (54)	CP 680-160/6"N	2/4	
2 (51)	2 (51)	CP 680-M 6", CP 680-P 6"	3/4	
4 (100)	1 (25)	CP 680-160/6"N	2/4	
4 (102)	1 (25)	CP 680-M 6", CP 680-P 6"	3/4	
d on the outside with an all service d with metal fasteners or with butt to be and Equipment Covering-Materia	jacket. Longitudinal joints sea ape supplied with the product. als (BRGU) category in the Bu and bearing the UL Classifical	ow cylindrical heavy density (min 3.5 pcf or 56 led with metal fasteners or factory-applied SS iilding Materials Directory for names of manufition Marking with a Flame Spread Index of 25 (38 mm) thick glass fiber pipe insulation in a	SL tape. Transverse jacturers. Any pipe of	

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Reproduced by HILTI, Inc. Courtesy of Hilti Firestop Systems

Refer to the following specifications for firestopping. a. 07 84 00 Firestopping

b. 07 84 13 Penetration Firestopping

c. 07 84 43 Joints Firestopping d. 22 00 00 Plumbing

g. 27 05 37 Communication Systems For Quality Control requirements, refer to the Quality Control portion of the

e. 23 00 00 HVAC

specification.

f. 26 00 00 Electrical

Details shown are typical details. Always refer to the listed system detail for complete system requirements. If field conditions do not match requirements of details, approved alternate details shall be utilized. Design requirements, field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following: Fire Rating (F-Rating)

Temperature Rating (T-Rating)

Leakage Rating (L-Rating)

Water Rating (W-Rating) **Annular Space** 

Percent Fill

Type and thickness of fire-rated construction.

If alternate details matching the field conditions are not available manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

References:

2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.

NFPA 101 Life Safety Code

building codes.

construction being penetrated.

NFPA 70 – National Electric Code

All governing local and regional

5. Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of

All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information.

Warning! - Do Not Disturb **Through Penetration Firestop** 

UL System # \* Product(s) used

Hourly Rating (F-Rating)

**Installation Date** Contractor's Name

For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as classified by Underwriter's Laboratories,

Fire Resistance Directory (Volume 1).

Current as of November 19, 2017. System details subject to change without notice.

JOB NUMBER: **DRAWN**: **CHECKED: ISSUE DATE: 01-25-2018** 


o designer (delete this natural). Any modification to the UL or Intertek Classifical. Details shown are up to For additional informational caboratories Fire Resistance.

**REVISIONS:** 

SHEET NAME:

**SHEET NUMBEF** 

4.1



Floor Assembly — Min 2-1/2 in. (64 mm) to max 8 in. (203 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m³) concrete. When concrete thickness is min 4-1/2 in. (114 mm), F Rating is 3 hr. A. Floor Assembly — (Optional, Not Shown) — The fire rated concrete and steel deck floor assembly shall be constructed of the materials and i the manner specified in the individual D700, D800 or D900 Series designs in the UL Fire Resistance Directory and as summarized below: A. Concrete — Min 2-1/2 in. (64 mm) to max 8 in. (203 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m³) concrete, as measured over crest of fluted steel deck. When concrete topping thickness is min 4-1/2 in. (114 mm), the F and FH Ratings are B. Steel Floor and Form Units\* — Composite or non-composite max 3 in. (76 mm) deep galv steel fluted units as specified in the individual t. Metallic Sleeve — (Optional, Not Shown) - Nom 4, 5 or 6 in. (102, 127 or 152 mm) diam Schedule 10 (or heavier) steel sleeve cast or grouted into floor assembly, flush with floor surfaces. When metallic sleeve is used, the T, FT and FTH Ratings are 0 Hr.

A. Sheet Metal Sleeve — (Optional, Not Shown) - Nom 4, 5, 6 or 9 in. (102, 127, 152 or 229 mm) diam, min 26 ga galv steel provided with a 26 ga

galy steel square flange spot welded to the sleeve at approx mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in, (51

mm) larger than the sleeve diam. The sleeve is to be cast in place and may extend a max of 4 in. (102 mm) below the bottom of the deck and

Hilti Firestop Systems

Reproduced by HILTI, Inc. Courtesy of

flush with the top surface of the concrete floor. When sheet metal sleeve is used, the T, FT and FTH Ratings are 0 Hr

1-3/4 in. (45 mm) long KWIK-BOLT 3 steel expansion anchor or Hilti 1/4 in. (6 mm) by 3/4 in. (19 mm) long Metal HIT Anchor may be used. In may be installed through the steel flange, two on each side. The firestop devices shall be installed as detailed in the following table: (Item 5 or 5A) or Tube (Item 4) and Thickness, or Sleeve Diam, Diam, In. (mm) In. (mm) In. (mm) 3/4 or 1 (19 or 25) AB/PVC CFS-DID 2"MD 3/4 or 1 (19 or 25) AB/PVC 3/4 or 1 (19 or 25) AB/PVC 3/4 or 1 (19 or 25) AB/PVC 1 (25) Glass Fiber 1 (25) Glass Fiber CFS-DID 3"MD 1-1/2 (38) Glass Fiber CFS-DID 4"MD 
 1 (25) Glass Fiber
 CFS-DID 4"MD


 2 (51) Glass Fiber
 CFS-DID 6"MD
 HILTI CONSTRUCTION CHEMICALS. DIV OF HILTI INC — CFS-DID 2"MD, CFS-DID 3"MD, CFS-DID 4"MD, CFS-DID 6"MD A. Steel Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 10 (or heavier) steel pip B. Iron Pipe — Nom 4 in. (102 mm) diam (or smaller) cast or ductile pipe. . Copper Tubing — Nom 4 in. (102 mm) diam (or smaller) Type L (or heavier) copper tubing D. Copper Pipe — Nom 4 in. (102 mm) diam (or smaller) Regular (or heavier) copper pipe. tube insulation material meeting the above specifications and having a UL94 Flammability Classification of 94-5VA may be used. jacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied SSL tape. Transverse joints secured with metal fasteners or with butt tape supplied with the product.

Reproduced by HILTI, Inc. Courtesy of

Smoke Developed Index of 50 or less may be used.

Bearing the UL Classification Mark

Hilti Firestop Systems



See Pipe and Equipment Covering-Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a assembly, flush with floor or wall surfaces or extending a max of 3 in. (76 mm) above floor or beyond both surfaces of wall. . Sheet Metal Sleeve — (Optional) Max 6 in. (152 mm) diam, min 26 ga. galv steel provided with a 26 ga galv steel square flange spot welded to the sleeve at approx mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in. (51 mm) larger than the sleeve diam. The sleeve is to be cast in place and may extend a max of 4 in. (102 mm) below the bottom of the deck and a max of 1 in. (25 mm) above the top 3. Sheet Metal Sleeve — (Optional) - Max 12 in. (305 mm) diam, min 24 ga galv steel provided with a 24 ga galv steel square flange spot welder to the sleeve at approx mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in, (51 mm) larger than the sleeve diam. The sleeve is to be cast in place and may extend a max of 4 in. (102 mm) below the bottom of the deck and a max of 1 in. (25 mm) above the top Through-Penetrant — One metallic pine, tube or conduit to be installed either concentrically or eccentrically within the fireston system. The annular space between penetrant and periphery of opening shall be min 0 in. (point contact) to max 1-7/8 in. (48 mm). Penetrant may be installed h continuous point contact. Penetrant to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic enetrants may be used: A. Steel Pipe — Nom 30 in. (762 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe. 3. Iron Pipe — Nom 30 in. (762 mm) diam (or smaller) cast or ductile iron pipe. Copper Pipe — Nom 6 in. (152 mm) diam (or smaller) Regular (or heavier) copper pipe Copper Tubing — Nom 6 in. (152 mm) diam (or smaller) Type L (or heavier) copper tubing.

. Conduit — Nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing (EMT

eproduced by HILTI, Inc. Courtesy of

System No. C-AJ-3095 ANSI/UL1479 (ASTM E814) F Rating — 3 Hr F Rating — 3 Hr Ratings — 0, 1/2 and 3/4 Hr (See Item 3) FT Ratings - 0, 1/2 and 3/4 Hr (See Item 3 Ratings - 0, 1/2 and 3/4 Hr (See Item


min 3 in. (76 mm) thick reinforced lightweight or normal weight concrete wall. Wall may also be constructed of any UL Classified Concrete Blocks\* ee Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers. 2. Sleeve — (Optional) — Nom 6 in. (152 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe cast or grouted into floor or wall assembly, flush with floor or wall surfaces or extending a max 3 in. (76 mm) above the floor or both surfaces of the wall. If the steel sleeve extends above the floor r both surfaces of the wall, the T Rating of the firestop system is 0 Hr. 5 Cables — Aggregate cross-sectional area of cables in opening to be min 25 percent to max 45 percent of the aggregate cross-sectional area of the opening. Cables to be rigidly supported on both sides of floor or wall assembly. Any combination of the following types and sizes of metallic A Max 500 kcmil single copper connector power cable with thermoplastic insulation and polyvinyl chloride (PVC) jacket. When single copper . Max 350 kcmil single conductor power cables with either aluminum or copper conductors and cross-linked polyethylene (XPLE) insulation. When single aluminum conductor power cable is used, T Rating is 0 hr. When single copper conductor power cable is used, T, FT and FT : Max 300 pair No. 24 AWG copper conductor telecommunication cables with polyvinyl chloride (PVC) insulation and jacket material. When telecommunication cable is used. T. FT and FTH Rating is 0 hr

. Floor or Wall Assembly — Min 2-1/2 in. (64 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600 2400 kg/m3) concrete floor or

. Max three copper connector No. 6 AWG cable with polyvinyl chloride (PVC) insulation and jacket material. When multi-connector power Max 7/C copper conductor No. 12 AWG multiconductor power and control cables with PVC or cross-linked polyethylene (XLPE) insulation and PVC jacket. When multiconductor power and control cable is used, T, FT and FTH Rating is 3/4 hr. . Multiple fiber optical communication cables jacketed with PVC and having a max outside diam of 1/2 in. When fiber optic cable is used, T, F1 G. Max 3/C copper conductor No. 12 AWG with Bare aluminum ground, polyvinyl chloride (PVC) insulated steel, Metal-clad cable+. When MC FC CABLE SYSTEMS INC

System No. C-AJ-5091 ΓH Ratings — 0 and 1 Hr (See Items 2 and L Rating At Ambient -4 CFM/s L Rating At 400 F -Less Than 1 CFM/sq

Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m³) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 29 in. (737 mm) See Concrete Blocks (CAZT) category in the Fire Resistance directory for names of manufacturers. 2. Metallic Sleeve — (Optional) — Nom 30 in. (762 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe sleeve cast or grouted into floor or wall assembly, flush with floor or wall surfaces or extending a max of 3 in. (76 mm) above floor or beyond both surfaces of wall. If the steel sleeve tends beyond the top surface of the floor or both surfaces of the wall, the T Rating of the firestop system is 0 hr. A. Sheet Metal Sleeve — (Optional) - Max 6 in. (152 mm) diam, min 26 ga galy steel provided with a 26 ga galy steel square flange spot welded to the sleeve at approximately mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in. (51 mm) larger than the sleeve diam. The sleeve is to be cast in place flush with bottom surface of floor and may extend a max of 1 in. (25 mm) above the top surface of the floor. 2B. Sheet Metal Sleeve — (Optional) - Max 12 in. (305 mm) diam, min 24 ga galy steel provided with a 24 ga galy steel square flange spot welded to the sleeve at approximately mid-height, or flush with bottom of sleeve in floors, and sized to be a min of 2 in. (51 mm) larger than the sleeve iam. The sleeve is to be cast in place flush with bottom surface of floor and may extend a max of 1 in. (25 mm) above the top surface of the floo



Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete floo or min 5 in. (127 mm) reinforced lightweight or normal weight concrete wall. Wall may also be constructed of any UL Classified Concrete Blocks\*. Floor may also be constructed of any min 6 in. (152 mm) thick UL Classified hollow core Precast Concrete Units\*. Max area of square, rectangular or circular opening is 192 sq in. (1239 cm2) with max dimension of 24 in. (61 cm). When Precast Concrete Unit floors are used, max area of square, rectangular or circular opening is 49 sq in. (316 cm2) with max dimension of 7 in. (17.8 cm). See Concrete Blocks (CAZT) and Precast Concrete Units (CFTV) categories in the Fire Resistance Directory for names of manufacturers. Through-Penetrant — One or more pipes or tubes to be installed within the opening. The total number of through-penetrants is dependent on the size of the opening and types and sizes of the penetrants. Any combination of the penetrants described below may be used provided that the following parameters relative to the annular spaces and the spacings between the pipes are maintained. The separation between cable bundle tubes and insulated tubes shall be a min 1/2 in. (13 mm) to max 3-1/8 in. (79 mm). The annular space between penetrants and the periphery pening shall be a min 1/2 in. (13 mm) to max 5 in. 127 mm). Pipes or tubes to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic pipes or tubes may be used. A. Copper Tubing — Nom 3 in. (76 mm) diam (or smaller) Type L (or heavier) copper tube. B. Copper Pipe — Nom 3 in. (76 mm) diam (or smaller) Regular (or heavier) copper pipe Steel Pipe — Nom 3 in. (76 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe. D. Iron Pipe — Nom 3 in. (76 mm) diam (or smaller) cast or ductile iron pipe. Conduit — Nom 3 in. (76 mm) diam (or smaller) electric metallic tubing (EMT) or steel conduit.

F. Flexible Steel Conduit+ — Nom 1 in (25 mm) diameter (or smaller) flexible steel conduit See Flexible Metal Conduit (DXUZ) category in the Electrical Construction Material Directory for names of manufacturers. Through Penetrating Product\* — Flexible Metal Piping — The following types of steel flexible metal gas piping may be used:

Reproduced by HILTI, Inc. Courtesy of

Firestop System — The firestop system shall consist of the following: A. Packing Material — Min 4 in. (102 mm) thickness of min 4 pcf (64 kg/m³) mineral wool batt insulation firmly packed into opening as a permanent form. Packing material to be recessed from top surface of floor or sleeve or from both surfaces of wall or sleeve as required to accommodate the required thickness of fill material. Fill, Void or Cavity Material\* — Sealant — Min 1/4 in. (6 mm) thickness of fill material applied within the annulus, flush with top surface of floor or sleeve or with both surfaces of wall or sleeve. At the point or continuous contact locations between penetrant and concrete or sleeve a min 1/4 in. (6 mm) diam bead of fill material shall be applied at the concrete or sleeve/ pipe penetrant interface on the top surface of floor HILTI CONSTRUCTION CHEMICALS. DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Reproduced by HILTI, Inc. Courtesy of

System No. C-AJ-3095

H. Max 3/C with ground 2/0 AWG copper conductor SER cable with cross-linked polyethylene (XLPE) insulation and polyvinyl chloride (PVC

. Max RG/U coaxial cable with polyethylene (PE) insulation and polyvinyl chloride (PVC) jacket having a max outside diameter of ½ in. When

J. Fire Resistive Cables\* - Max 1-1/4 in. (32 mm) diam single conductor or multi conductor Type MI cable. A min 1/8 in. (3 mm) separation shall

be maintained between MI cables and any other type of cable. When Fire Resistive Cables \*are used, T, FT and FTH Rating is 0 hr.

See Through Penetrating Product (XHLY) category in the Fire Resistance Directory for names of manufacturers.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant

steel sleeve (Item 2) extends above the top of the floor, the packing material shall be flush with the bottom surface of the floor.

C. Through Penetrating Product\* — Any Cables, Metal-Clad Cable+ or Armored Cable+ currently Classified under the Through Penetrating

Packing Material — Min 2 in. (51 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into opening as a permanen

5. Fill, Void or Cavity Material\* — Sealant — Min 1/2 in. (13 mm) thickness of fill material applied within the annulus, flush with top surface of floor c

eproduced by HILTI, Inc. Courtesy of

System No. C-AJ-5091

Through Penetrants — One metallic pipe or tubing to be installed either concentrically or eccentrically within the firestop system. Pipe or tubing to

. Pipe Covering — Min 1/2 in. (13 mm) to max 2 in. (51 mm) thick hollow cylindrical heavy density (min 3.5 pcf or 56 kg/m³) glass fiber units acketed on the outside with an all-service jacket. Longitudinal joints sealed with metal fasteners or factory-applied, self-sealing lap tape.

ransverse joints secured with metal fasteners or with butt tape supplied with the product. The annular space between the insulated pipe and th edge of the periphery of the opening shall be min 1/2 in. (13 mm) to max 12 in. (305 mm). When thickness of pipe covering is less than 2 in. (51

See Pipe Equipment Covering — Materials — (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe

Pipe Covering — (Not Shown) — As an alternate to Item 4, max 2 in. (51 mm) thick cylindrical calcium silicate (min 14 pcf or 224 kg/m³) units sized to the outside diam of the pipe or tube may be used. Pipe insulation secured with stainless steel bands or min 18 AWG stainless steel wire

permanent form. Packing material to be recessed from top surface of floor or from both surfaces of wall as required to accommodate the

3. Fill, Void or Cavity Material\* — Sealant — Min 1/2 in. (13 mm) thickness of fill material applied within the annulus, flush with top surface of

Reproduced by HILTI, Inc. Courtesy o

System No. C-AJ-8099

A. Packing Material — Min 4 in. (102 mm) thickness of min 4 pcf (64 kg/m³) mineral wool batt insulation firmly packed into opening as a

ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant

covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a

be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic pipes or tubing may be used:

A. Steel Pipe — Nom 12 in. (305 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe.

. Copper Tubing — Nom 6 in. (152 mm) diam (or smaller) Type L (or heavier) copper tubing

spaced max 12 in. (305 mm) OC. The annular space shall be min 1/2 in. (13 mm) to max 12 in. (305 mm).

B. Iron Pipe — Nom 12 in. (305 mm) diam (or smaller) cast or ductile iron pipe. . Copper Pipe — Nom 6 in. (152 mm) diam (or smaller) Regular (or heavier) copper pipe

mm), the T Rating for the firestop system is 0 hr.

floor or with both surfaces of wall.

Smoke Developed Index of 50 or less may be used.


estop System — The firestop system shall consist of the following:

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada)

form. Packing material to be recessed 1/2 in. (13 mm) from top surface of floor or from both surfaces of wall to accommodate the fill material. If the

jacket. When SER cable is used, T, FT and FTH Rating is 0 hr.

System No. C-AJ-1226



Min 5 in. (127 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete wall. Wall may also be constructed or any UL Classified Concrete Blocks\*, Max size of opening is 8 in. (203 mm) by 30 in. (763 mm). See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers Through Penetrants — One or more metallic penetrants to be installed either concentrically or eccentrically within the firestop system. The tota number of penetrants is dependent on the size of the opening and sizes of penetrants. The annular space between the penetrants and peripher of opening shall be min 0 in. (point contact). The annular space between nom 2 in. (51 mm) diam (and smaller) penetrants shall be a min 0 in. oint contact). The annular space between penetrants greater than nom 2 in. (51 mm) diam shall be a min. 1/2 in. (13 mm). A max annular spa in the system shall be 12 in. (305 mm). Penetrants to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of Conduit — Nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing or rigid steel conduit B. Through Penetrating Product\* — Flexible Metal Piping — The following types of steel flexible metal gas piping may be used:

System No. C-AJ-1513

CAN/ULC S115

F Rating - 2 I

FTH Rating - 0 I

FT Ratings — 0 and 1/2 Hr (See Item

FTH Ratings - 0 and 1/2 Hr (See Item 2

L Rating At Ambient — Less Than 1 CFM (See Item 2

L Rating At 400 F — Less Than 1 CFM (See Item 2

FT Rating — 0 I

FH Rating — 2 H

1.) Nom 2 in. (51 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both side 2.) Nom 1 in. (25 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both side GASTITE, DIV OF TITEFLEX 3.) Nom 2 in. (51 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both sides of floor or wall assembly.

Firestop System — The firestop system shall consist of the following: A. Packing Material — Min 4 in. (102 mm) thickness of 4 pcf (64 kg/m3) mineral wool batt insulation tightly packed into the opening as a permanent form. Packing material to be recessed from top surface of floor or both surfaces of wall to accommodate the required thickness of B. Fill, Void or Cavity Material - Sealant\* — Min 1/2 in. (13 mm) thickness of fill material applied within the annulus flush with the top surface of HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada)

System No. C-AJ-3283

1. Floor or Wall Assembly — Min 2-1/2 in. (64 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete. Wa

1A. Floor Assembly — (Not Shown) — As an alternate to Item 1, fire-rated unprotected concrete and steel floor assembly may be used. Floor

A. Concrete — Min 2-1/2 in. (64 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete.

B. Steel Floor and Form Units — Composite or noncomposite max 3 in. (76 mm) deep fluted galy units as specified in the individual Floor-Ceiling design. Opening in floor or wall to be max 3 in. (76 mm) diam for 2" device and max 5 in. (127 mm) diam for 4" device.

Reproduced by HILTI, Inc. Courtesy of

System No. C-AJ-6042

Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete floo

or wall. Wall may also be constructed of any UL Listed Concrete Blocks\*. Max area of opening is 240 in.2 (1548 mm2) with max dimension of 30

I-1/2 in. (114 mm) deep, "I" shaped aluminum enclosure containing factory mounted aluminum bars rated for 600 V, 4000A or copper bars rate

for 600 V, 5000 A. When two busways are installed, they shall be placed end to end and the annular space between busways shall be min 1/2 i

(13 mm). The annular space between busways and periphery of opening shall be min 1/4 in. (6 mm) to max 5-3/4 in. (146 mm). Busways to be

rigidly supported on both sides of floor and wall assembly. The busways shall bear the UL Listing Mark and shall be installed in accordance with

A. Fill, Void or Cavity Material\* — Fire blocks installed with 5 in. (127 mm) dimension passed through the opening and centered within the

thickness of the floor or wall. In concrete block walls, fire block to fill entire thickness of wall opening unless wall is solid filled. Blocks to be

B. Fill, Void or Cavity Material\* — (Not Shown) - Fill material to be applied to maximum extent possible within the opening between and around

busways and fire block to fill any voids. This fill material is to be applied from the top surface of the floor assembly or both surfaces of wall

Reproduced by HILTI, Inc. Courtesy of

System No. C-AJ-8143

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Intumescent Sealant or FS-ONE MAX Intumescent Sealant

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

2. Busway — One nom 23 in. (584 mm) wide (or smaller) by 4-1/2 in. (114 mm) deep, or max two nom 11-1/4 in. (286 mm) wide (or smaller) by

See Concrete Blocks (CAZT) in the UL Fire Resistance Directory for names of manufacturers.

firmly packed and completely fill the entire area of opening between and around busways

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CFS-BL Firestop Block

the National Electrical Code, NFPA No. 70.

Firestop System — The firestop system shall consist of the following

assembly to be constructed of the materials and in the manner described in the individual D900 Series Floor-Ceiling Design in the UL Fire

See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.

Resistance Directory and shall include the following construction features:

127 mm) diam for 4" device.

Hilti Firestop Systems


may also be constructed of any UL Classified Concrete Blocks\*. Opening in floor or wall to be max 3 in. (76 mm) diam for 2" device and max 5 i

produced by HILTI, Inc. Courtesy of

ANSI/UL1479 (ASTM E814)

Rating At 400 F - Less Than 1 CFM (See Item 2

Ratings — 0 and 1/2 Hr (See Item 2



W Rating does not apply when the steel sleeve is used. . Through Penetrants — One nonmetallic pipe to be installed either concentrically or eccentrically within the firestop system. For max 6 in. (152 mm) diam pipes, the annular space between the pipe and the periphery of opening shall be min 0 in. (0 mm, point contact) to max 1/2 in. (13 mn For nom 8 in, (203 mm) and 10 in, (254 mm) diam pipes, the annular space between the pipe and the periphery of opening shall be min 0 in, (0 mm, point contact) to max 1-1/4 in. (32 mm). If the steel sleeve extends above the floor (Item 2), a min 1/2 in. (13 mm) annular space is required between the through penetrant (Item 3) and the periphery of the opening. Pipe to be rigidly supported on both sides of floor or wall assembly. For systems with a W Rating, the max annular space is 1/2 in. (13 mm). The T Ratings are dependent on the size and/or type of pipe as shown in the table below. The following types and sizes of nonmetallic pipes may be used: A. Polyvinyl Chloride (PVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) Schedule 40 solid core or cellular core PVC pipe for use in closed (process or supply ) or vented (drain, waste or vent) piping systems. For systems with a W Rating, the nom diam of pipe shall not exceed 6 in. B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems. For systems with a W Rating, the nom diam of pipe shall not exceed 6 in. (152 mm). . Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system. . Flame Retardant Polypropylene (FRPP) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process of supply) or vented (drain, waste or vent) piping systems.

produced by HILTI, Inc. Courtesy of

D. Max 4 pr No. 22 AWG Cat 6 computer cables.

K. Max 3/C No 12 AWG MC Cable.

System No. C-AJ-3283 . Cables — Within the loading area for the firestop device, the cables may represent a 0 to 100 percent visual fill. Cables to be tightly bundled within the device and rigidly supported on both sides of floor or wall assembly. Any combination of the following types of cables may be used: A. Max 100 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation. B. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation C. Max 4/0 AWG Type RHH ground cable.

E. Max RG 6/U coaxial cable with fluorinated ethylene insulation and jacketing. F. Fiber optic cable with polyvinyl chloride (PVC) or polyethylene (PE) jacket and insulation having a max diam of 1/2 in. (13 mm). G. Max 20/C No. 22 AWG shielded printer cable with PVC jacket 4. Through-Penetrating Product\* — Two copper conductors No. 18 AWG (or smaller) Power or Non Power Limited Fire Alarm Cable with or without a jacket under a metal armor I. Max 1/4 in. (6 mm) diameter S-Video Cable consisting of 2 max 24 AWG 75 ohm coax or twisted pair cable with PE insulation and PVC jacket . Through Penetrating Product\* — Any Cables, Metal-Clad Cable+ or Armored Cable+ currently Classified under the Through Penetrating

See Through Penetrating Product (XHLY) category in the Fire Resistance Directory for names of manufacturers

Ratings.						
	Max Cable	Cable Type	L Rating, 0	CFM/Sq Ft	L Rating, CFM	
	Fill	Саые туре	Ambient	400°F	Ambient	400°F
	0%		1	2	Less than 1	Less than 1
	100%	Any cables (Item 2) in any	7	7	Less	Less


Firestop Device\* — Firestop device consists of a corrugated steel tube with an inner plastic housing, intumescent material rings, tightly twisted


nner fabric smoke seal, flanges and gasket material (not shown). Firestop device to be installed in accordance with the accompanying installat

e T, FT and FTH Ratings for the firestop system are 1/2 hr except that when cable types 2J or 2K are used, the T, FT and FTH Ratings are 0 hr

istructions. Device slid into floor or wall such that ends project an equal distance from the approximate centerline of the assembly. The annular space between the device and the periphery of the opening shall be min 0 in. (point contact). Device provided with flange(s) that are spun clockwise onto device threads, over gasket material butting tightly to top side of floor or both sides of wall. In floors, when FS-ONE Sealant is used and installed flush with bottom of floor, device flange shall be threaded tightly to bottom side of floor. In floors, device flange to be secured to floor with min two 1-1/4 in (32 mm) long steel masonry screws or anchors. As an alternate to gasket material, sealant (Item 4) may be used HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 653 and CP 653 BA 2" Speed Sleeve, CP 653 and CP 653 BA 4" Speed Sleeve annulus between fireston device and periphery of opening, flush with top surface of floor or both sides of wall. As an option, when FS-ONE Sealant is used, the fill material can be installed flush with bottom of floor. For L Ratings when sealant is used, an additional 1/4 in, (6 mm) bea of fill material is applied at the device/floor or device/wall interface on top or bottom side of floor or both sides of wall assembly prior to installing HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 618 Firestop Putty, FS-ONE Sealant or FS-ONE MAX Intumescent Sealant. Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

produced by HILTI, Inc. Courtesy of





. Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete floo or min 5-1/2 in. (140 mm) thick lightweight on normal weight concrete wall. Wall may also be constructed of any UL Classified Concrete Block: Max area of opening is 1024 in, sq (6606 cm2) with a max dimension of 32 in, (813 mm). See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers Steel Duct — Nom 30 by 30 in. (762 by 762 mm) by No. 24 gauge (or heavier) galv steel duct. One steel duct to be positioned within the firest system. The annular space shall be min 1/4 in. (6 mm) to max 1-3/4 in. (44 mm). Duct to be rigidly supported on both sides of floor or wall

Firestop System — The firestop system shall consist of the following: A. Packing Materials — Min 3-1/2 in. (89 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into opening as a permanent form between the bare steel duct and the periphery of the opening. Packing material to be recessed from top surface of floor or B. Fill, Void or Cavity Material\* — Sealant — Min 1 in. (25 mm) thickness of fill material applied within the annulus, flush with top surface of floor or with both surfaces of wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 606 Flexible Firestop Sealant, FS-ONE Sealant or FS-ONE MAX Intumesco . Steel Retaining Angle — Nom 2 in. by 2 in. (51 by 51 mm) by No. 16 gauge (or heavier) steel angles attached to all four sides of the steel duct of the top surface or both surfaces of the wall. The angles shall be attached with No. 8 (or larger) steel sheet metal screws spaced max of 1 in. (25 Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

eproduced by HILTI, Inc. Courtesy of lerwriters Laboratories, Inc

## System No. C-AJ-8143


1. Max 500 kcmil single copper or aluminum conductor power cable with thermoplastic insulation and polyvinyl chloride (PVC) jacket. 2. Max 300 pair No. 24 AWG copper conductor telecommunication cables with PVC insulation and jacket material. 3. Max 7/C copper conductor No. 12 AWG multi-conductor power and control cables with PVC or cross-linked polyethylene (XLPE) insulation 4. Multiple fiber optical communication cables jacketed with PVC and having a max outside diam of 1/2 in. 5. Max 3/C No. 12 AWG steel dad cable with copper conductors and PVC insulation material.

Individual Cables — Any of the following types and sizes of individual (non-bundled) cables may be used: 1. Max 3/C No. 2/0 AWG (or smaller) copper conductor PVC jacketed aluminum clad or steel clad TECK 90 cable Through Penetrating Product\* — Any cables, Armored Cable+ or Metal Clad Cable+ currently Classified under the Through Penetrating See Through Penetrating Product (XHLY) category in the Fire Resistance Directory for names of manufacturers Max 500 kcmil single copper or aluminum conductor power cable with thermoplastic insulation and polyvinyl chloride (PVC) jacket

4. Max 300 pair No. 24 AWG copper conductor telecommunication cables with PVC insulation and jacket material. 5. Max 7/C copper conductor No. 12 AWG multi-conductor power and control cables with PVC or cross-linked polyethylene (XLPE) insulation 6. Multiple fiber optical communication cables jacketed with PVC and having a max outside diam of 1/2 in . Max 3/C No. 12 AWG steel clad cable with copper conductors and PVC insulation material.

Any combination of the types and sizes of cables described in Item 2B may be used. Cable tray to be rigidly supported on both sides of floor or A. Pipe Covering\* — Nom 1-1/2 in. (38 mm) thick (or thinner) hollow cylindrical heavy density glass fiber units jacketed on the outside with an all service jacket for pipes with a nom diam of 8 in. (203 mm) (or smaller) or tubes with a nom diam of 4 in. (102 mm) (or smaller). Longitudinal joints sealed with metal fasteners or factory-applied self-sealing lap tape. Transverse joints secured with metal fasteners or with butt tape See Pipe and Equipment Covering - Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used. B. Pipe Covering\* — Nom 2 in. (51 mm) thick (or thinner) hollow cylindrical heavy density glass fiber units jacketed on the outside with an all service jacket for pipes or tubes with a nom diam of 2 in. (51 mm) (or smaller). Longitudinal joints sealed with metal fasteners or factory-applied See Pipe and Equipment Covering - Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used. C. Tube Insulation-Plastics+ — Nom 1 in. (25 mm) thick (or thinner) acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible foam furnished in the form of tubing for pipes or tubes with a nom diam of 2 in. (51 mm) (or smaller). See Plastics (QMFZ2) category in the Plastics Recognized Component Directory for names of manufacturers. Any Recognized Component tube


eproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 15, 2015




Rating and/or L Rating, min 1/2 in, (13 mm) thickness of CP 601S, CFS-S SIL GG, CFS-S SIL SL (floors only) or CP 604 Sealant shall be applied within the annulus, flush with top or bottom surface of floor. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant, FS-ONE MAX Intumescent Sealant, CP 601S Sealant, CFS-S SIL GG, CFS-S SIL SL (floors only) or CP 604 Sealant 4A. Packing Material (not shown) - Min 1/2 in. (13 mm) thickness of 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into annular space and recessed from the top surface of floor to accommodate the required thickness of fill material. Required only when CP 604 Sealant is used 5. Firestop Device\* — Firestop Collar — Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to underside of floor or both sides of wall using the anchor hooks provided with the collar. 102 mm) diam pipes. Minimum four anchor hooks required for nom 6 in. (152 mm) diam pipes. Minimum ten anchor hooks required for nom 8 in (203 mm) diam pipes. Minimum twelve anchor hooks required for nom 10 in. (254 mm) diam pipes. The anchor hooks are to be secured with mir 4 in. (6 mm) diam by min 1-1/4 in. (32 mm) long steel expansion bolts or min 0.145 in. (3.7 mm) diam by 1-1/4 in. (32 mm) long powder actuate fasteners utilizing a 1-7/16 in. (37 mm) diam by 1/16 in. (1.6 mm) thick steel washer. As alternates to the anchors specified above, Hilti 1/4 in. (6 mm) diam by 1-1/4 in, (32 mm) long KWIK-CON II+ concrete screw anchor, Hilti 1/4 in, (6 mm) diam by 1-3/4 in, (45 mm) long KWIK-BOLT 3 steel expansion anchor or Hilti X-DNI 27 P8 S15 powder actuated floor pin with integral nom 9/16 in. (15 mm) diam washer may be used. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 643N 50/1.5", CP 643N 63/2", CP 643N 90/3", CP 643N 110/4", CP 643 160/6 CP 644 200/8" or CP 644 250/10" Firestop Collar

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

eproduced by HILTI, Inc. Courtesy of



eproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc




I. Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 21-3/4 in. (552 mm). See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers. duct and periphery of opening shall be 0 in. (point contact) and max 1-1/2 in. (38 mm). Duct to be rigidly supported on both sides of wall assembly A. Spiral Wound HVAC Duct — Nom 20 in. (508 mm) diam (or smaller) No. 24 MSG (or heavier) galv steel spiral wound duct.

A. Packing Material — Min 3-1/2 in. (89 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into opening as a

3. Firestop System — The firestop system shall consist of the following:

permanent form. Packing material to be recessed from top surface of floor or both surfaces of wall to accommodate the required thickness of B. Fill. Void or Cavity Material\*—Sealant — Min 1 in. (25 mm) thickness of fill material applied within annulus, flush with top surface of floor c both surfaces of wall assembly. At the point contact location between duct and periphery of opening, a min 1/2 in. (13 mm) diam bead of sealant shall be applied at the concrete/duct interface HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant, FS-ONE MAX Intumescent Sealant, CP601S Elastomer irestop Sealant, CP606 Flexible Firestop Sealant, CP 604 Self-Leveling Firestop Sealant, CFS-S SIL GG Sealant or CFS-S SIL SL Sealant.



may also be constructed of any UL Classified Concrete Blocks\*. Floor may also be constructed of any min 6 in. (152 mm) thick UL Classified hollow core Precast Concrete Units\* having a min 2 in. (51 mm) concrete thickness below the core. Max diam of opening is 3 in. (76 mm). See Concrete Blocks (CAZT) and Precast Concrete Units (CFTV) categories in the Fire Resistance Directory for names of manufacturers. . Through Penetrants — One nonmetallic pipe to be installed concentrically or eccentrically within the firestop system. Annular space between pipe and edge of opening to be min 0 in. (point contact) and max 5/8 in. (16 mm). Pipe to be rigidly supported on both sides of floor-ceiling assembly. The following types and sizes of nonmetallic pipes may be used. A. Polyvinyl Chloride (PVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 solid or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or 3. Fill. Void or Cavity Material\* — Sealant — Min 2 in. (51 mm) thickness of fill material applied within the annulus, flush with bottom surface of floo or with both surfaces of wall. At point contact location, min 1/2 in. (13 mm) diam bead of sealant applied at pipe/concrete interface on bottom HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC - FS-ONE Sealant or FS-ONE MAX Intumescent Sealant ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada).

Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete. Wa


eproduced by HILTI, Inc. Courtesy of

Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*, Max diam of opening is 18 in, (457 mm). See Concrete Blocks (CAZT) Category in the Fire Resistance Directory for names of manufacturers. . Metallic Sleeve — (Optional) — Nom 18 in. (457 mm) diam (or smaller) Schedule 10 (or heavier) steel sleeve cast or grouted into floor or wall assembly, flush with floor or wall surfaces or extending a max of 3 in. (76 mm) above floor or beyond both surfaces of wall. . Through Penetrants — One metallic pipe or tubing to be centered within the firestop system. Pipe or tubing to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic pipes or tubing may be used: A. Steel Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 5 (or heavier) steel pipe. B. Copper Pipe — Nom 4 in. (102 mm) diam (or smaller) Regular (or heavier) copper tubing. C. Copper Tubing — Nom 4 in. (102 mm) diam (or smaller) Type L (or heavier) copper tubing. . Tube Insulation — Plastics+ — Min 1/2 in. (13 mm) to max 3/4 in. (19 mm) thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible

foam furnished in the form of tubing. Nom 1 in. (25 mm) thick AB/PVC flexible foam insulation may be used for max 2 hr F and FH Ratings when max 3 in. (76 mm) diam pipe or tubing is used. The annular space shall be min 1/2 in. (13 mm) to max 12 in. (305 mm). When max annular space exceeds 1-1/2 in. (38 mm) the F and FH Ratings are 2 hr. See Plastics+ (QMFZ2) Category in the Recognized Component Directory for names of manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used. . Firestop System — The firestop system shall consist of the following: A. Packing Material — Min 4 in. (102 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into opening as a permanent form. Packing material to be recessed from top surface of floor or from both surfaces of wall as required to accommodate the B. Fill. Void or Cavity Material\* — Sealant — Min 1/4 in. (6 mm) thickness of fill material applied within the annulus, flush with top surface of

floor or with both surfaces of wall. When max annular space exceeds 1-1/2 in. (38 mm) the min thickness of fill material is 1/2 in. (13 mm). HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

eproduced by HILTI, Inc. Courtesy of



2. Steel Duct — Max 60 by 36 in. (1524 by 914 mm) steel duct. Steel gauge of duct shall conform with SMACNA requirements. One duct to be installed concentrically or eccentrically within the firestop system. The annular space between steel duct and edges of opening shall be min 2 in (51 mm) to max 6 in. (152 mm) when max duct dimension is 28 in. (711 mm). Otherwise, max annular space is 2-1/2 in. (64 mm). Steel duct to be rigidly supported on both sides of floor or wall assembly. Batts and Blankets\* — Nom 2 in. (51 mm) thick light density (min 3/4 pcf or 12 kg/m3) glass fiber blanket insulation jacketed on the outside with a foil-scrim-kraft facing. Longitudinal and transverse joints sealed with foil-scrim-kraft tape. Nom annular space between insulated steel duct and periphery of opening to be point contact to max 1/2 in. (13 mm) prior to installation of packing material (Item 4A). When max duct dimension is 28 See Batts and Blankets (BKNV) category in the Building Materials Directory for names of manufacturers. Any batt or blanket meeting the above specifications and bearing the UL Classification Marking with a Flame Spread value of 25 or less and a Smoke Developed value of 50 or less may

4. Firestop System — The firestop system shall consist of the following: A. Packing Material — Min 4 in (102 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into annular space such that glass fiber blanket insulation on steel duct is compressed to a maximum overall thickness of 1/2 in. (13 mm). Packing material to be recessed from top surface of floor and from both surfaces of wall to accommodate the required thickness of fill material. . Fill, Void or Cavity Material\* — Sealant — Min 1/2 in. (13 mm) thickness of fill material applied within the annulus, flush with top surface of floor and both surfaces of wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC - FS-ONE Sealant or FS-ONE MAX Intumescent Sealant Retaining Angles — Min 2 by 2 in. (51 by 51 mm) No. 16 ga (or heavier) galv steel angles. Angles attached to all four sides of steel duct through glass fiber blanket insulation, on top surface of floor or on both surfaces of wall with No. 10 (or larger) steel sheet metal screws spaced 1 in. (25 mm) from each end and max 4 in. (102 mm) OC. ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada).

January 13, 2015

eproduced by HILTI, Inc. Courtesy of

Refer to the following specifications for firestopping. a. 07 84 00 Firestopping b. 07 84 13 Penetration Firestopping c. 07 84 43 Joints Firestopping d. 22 00 00 Plumbing e. 23 00 00 HVAC f. 26 00 00 Electrical g. 27 05 37 Communication Systems

For Quality Control requirements, refer to the Quality Control portion of the specification.

2. Details shown are typical details. Always refer to the listed system detail for complete system requirements. If field conditions do not match requirements of details, approved alternate details shall be utilized. Design requirements, field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following: Fire Rating (F-Rating)

Temperature Rating (T-Rating)

Leakage Rating (L-Rating)

Water Rating (W-Rating) **Annular Space** 

Percent Fill

Type and thickness of fire-rated construction.

If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.

NFPA 101 Life Safety Code

NFPA 70 – National Electric Code

All governing local and regional building codes.

5. Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of construction being penetrated.

All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information

Warning! - Do Not Disturb **Through Penetration Firestop** 

UL System # \* Product(s) used

Hourly Rating (F-Rating) **Installation Date** 

Contractor's Name

For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as classified by Underwriter's Laboratories, Fire Resistance Directory (Volume 1).

Current as of November 19, 2017. System details subject to change without notice.

lesigner (delete this rangesigner) delete this rangement of the contraction of the contra

JOB NUMBER: DRAWN:

**CHECKED:** ISSUE DATE: 01-25-2018

SHEET NAME: Residential - Flat Deck Floors or Walls

SHEET NUMBER

1.) Nom 2 in. (51 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both sides 2.) Nom 1 in. (25 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both sides GASTITE, DIV OF TITEFLEX 3.) Nom 2 in. (51 mm) diam (or smaller) steel flexible metal gas piping. Plastic covering on piping may or may not be removed on both sides

of floor or wall assembly. he hourly T Rating is 3/4 hr when a pipe or tube with fiber-glass insulation is used, or 0 hr when a pipe or tube, a pipe or tube with AB/PVC nsulation or a cable bundle is used. The TRating is 0 hr when metallic penetrants without pipe insulation are used. pe Insulation — (Optional)—The following types of pipe insulation may be used with metallic penetrants (Items 2A, 2B, 2C, 2D and 2F): A. Pipe Covering\* — Nom 1 in. (25 mm) thick (or thinner) hollow cylindrical heavy density (min 3.5 pcf or 56 kg/m3) glass fiber units jacketed or the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing lap tape. Transverse joints covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used. 3. Tube Insulation-Plastics+++ — Nom 3/4 in. (19 mm) thick (or thinner) acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible foam See Plastics+++ (QMFZ2) category in the Plastics Recognized Component Directory for names of manufacturers. Any Recognized Component


furnished in the form of tubing. ube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used. . Cables — Max 2 in. (51 mm) diam tight bundle of cables installed within the opening and rigidly supported on both sides of floor or wall assembly. The space between the cables and periphery of the opening shall range from min 2 in. (51 mm) to max 4 in. (102 mm). Any combination of the Illowing types and sizes of metallic conductor of fiber optic cable may be used: A. Max 500 kcmil single copper connector power cable with thermoplastic insulation and polyvinyl chloride (PVC) jacket. B. Max 300 pair No. 24 AWG copper conductor telecommunication cables with PVC insulation and jacket material. C. Max 7/C copper conductor No. 12 AWG multiconductor power and control cables with PVC or cross-linked polyethylene (XLPE) insulation and PVC jacket

E. Max 3/C copper conductor No. 12 AWG with bare aluminum ground, PVC insulated steel Metal-Clad cable. Firestop System — The firestop system shall consist of the following: A Packing Material — Min 4 in (102 mm) thickness of min 4 pcf (64 kg/m3) mineral wool batt insulation firmly packed into opening as a permanent form. Packing material to be recessed from top surface of floor or both surfaces of wall to accommodate the required thickness of fill material. When Precast Concrete Unit floors are used, packing material shall be installed at a thickness equal to the thickness of the floor minus 1/2 in. (13 mm), flush with bottom surface of floor. 3. Fill Void or Cavity Materials\* - Sealant — Min 1/2 in. (51 mm) thickness of fill material applied within the annulus, flush with top surface of HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant. ++Bearing the UL Recognized Component Marking

D. Multiple fiber optical communication cables jacketed with PVC and having a max outside diam of 1/2 in.

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada). Bearing the UL Listing Mark

Reproduced by HILTI, Inc. Courtesy of



L Classified Concrete Blocks\*. Max size of opening is 1440 in.2 (9,290 cm2) with a max dimension of 48 in. (1219 mm). etrants may be used. A. Metallic Pipes — The following types of metallic pipes, tubes or conduits may be used: 1. Copper Tubing — Nom 6 in. (152 mm) diam (or smaller) Type L (or heavier) copper tube.

Floor or Wall Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete floor. M 5 in. (127 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) concrete wall. Wall may also be constructed of any . Through-Penetrant — One cable tray and one or more pipes, tubes or cable bundles may be installed within the opening. The total number of ough-penetrants is dependent on the size of the opening and the types and sizes of the penetrants. Any combination of the penetrants describe below may be used provided that the following parameters relative to the annular spaces are maintained. The annular space between cable tray ar all other penetrants shall be min 3 in. (76 mm). The annular space between individual cables and cable bundles shall be a min 1/2 in. (13 mm). The annular space between individual cables and cable bundles and other penetrants shall be a min 1/2 in. (13 mm) except that a min 2 in. (51 mm) shall maintained between the cables and copper pipes and tubes greater than a nom 3 in. (76 mm) diam and steel and iron pipes and conduits greater nan a nom 4 in. (102 mm) diam. The annular space between metallic pipes, conduit and tubes and insulated pipes and tubes shall be a min 2 in. 🤃 mm). The annular space between nom 3 in (76mm) diam (and smaller) copper pipes and tubes and between nom 4 in (102mm) diam (and smaller) eel and iron pipes and conduits shall be min 1/2 in. (13 mm). The annular space between nom 2 in. (51 mm) diam (and smaller) metallic pipes an onduits shall be min 0 in. (point contact). The annular space between insulated penetrants or the cable tray and the periphery of opening shall be min /2 in. (13 mm). The annular space between all other penetrants and the periphery of opening shall be min 0 in. (point contact). A max annular space in the system shall be 12 in. (305 mm). Penetrants to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of 2. Copper Pipe — Nom 6 in (152 mm) diam (or smaller) Regular (or heavier) copper pipe 3. Steel Pipe — Nom 24 in. (610 mm) diam (or smaller) Schedule 40 (or heavier) steel pipe. 4. Iron Pipe — Nom 24 in. (610 mm) diam (or smaller) cast or ductile iron pipe. 5. Conduit — Nom 4 in. (102 mm) diam (or smaller) electric metallic tubing (EMT) or nom 6 in. (152 mm) diam (or smaller) rigid steel conduit.


Reproduced by HILTI, Inc. Courtesy of


derwriters Laboratories, Inc. January 15, 2015

supplied with the product.

8 Max 4C/750 kcmil (or smaller) aluminum or copper conductor metal clad cable with aluminum or steel armor, with or without PVC jacke D. Cable Tray\* — (Not Shown) — Max 24 in. (610 mm) wide by 6 in. (152 mm) deep open-ladder steel or aluminum cable tray. Aggregate ross-sectional area of cable tray to be max 40 percent of the cross-sectional area of the cable tray based on a max 3 in. cable loading dep Pipe Insulation — (Optional) - Pipes and tubes of the sizes noted below may be provided with one of the following types of pipe insulations:: self-sealing lap tape. Transverse joints secured with metal fasteners or with butt tape supplied with the product. insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used. Firestop System — The firestop system shall consist of the following: A. Packing Material — Min 4 in. (102 mm) thickness of 4 pcf (64 kg/m3) mineral wool batt insulation tightly packed into the opening as a permanent form. Packing material to be recessed from top surface of floor or both surfaces of wall to accommodate the required thickness of 3. Fill, Void or Cavity Material - Sealant\* — Min 1/2 in. (13 mm) thickness of fill material applied within the annulus flush with the top surface of the HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant, Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada)

(Note: CP 604 Self-Leveling Firestop Sealant and CFS-S SIL SL Sealant to be used on floor assemblies only.) \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), Reproduced by HILTI, Inc. Courtesy of January 28, 2015





with both surfaces of wall. At the point contact location between pipe covering and gypsum board, a min 1/2 in. (13 mm) diam bead of fill material

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Reproduced by HILTI, Inc. Courtesy

System No. W-L-8079

System tested with a pressure differential of 2.5 Pa between the exposed and the unexposed surfaces with the higher pressure on the exposed

1. Wall Assembly — The 1 or 2 hr fire rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in

the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following

A. Studs — Wall framing may consist of either wood studs or channel shaped steel studs. Wood studs to consist of nom 2 by 4 in, (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC. When Item

B. Gypsum Board\* — 5/8 in. (16 mm) thick with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type

framing members are used to frame the opening, the hourly T, FT and FTH Ratings of the firestop system are 0 hr.

5A1 is not used, additional framing members (not shown) shall be installed to frame the periphery of the wall opening. When the additional


FH Ratings - 1 and 2 Hr (See Item

H Ratings — 0, 1/2, 3/4, 1-1/2 and 2 Hr (See Items 1,

ANSI/UL1479 (ASTM E814

shall be applied at the pipe covering/gypsum board interface on both surfaces of wall.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant



ANSI/UL1479 (ASTM E814)

ANSI/UL1479 (ASTM E814)

1. Wall Assembly — The 1 or 2 hr fire-rated gyosum board/stud wall assembly shall be constructed of the materials and in the manner described in

B. Gypsum Board\* — Thickness, type, number of layers and fasteners, as specified in the individual Wall and Partition Design. Max height o

2. Through Penetrants — Multiple pipes or conduits installed in single layer array within the firestop system. The annular space between the pipe: and conduits and the edges of the opening shall be min 0 in. (0 mm, point contact) to max 1-3/8 in. (35 mm). The separation between pipes and

conduits to be a min 0 in. (0 mm. point contact) to a max 1-1/4 in. (32 mm). Pipes and conduits to be rigidly supported on both sides of wall

3. Fill Void or Cavity Materials\* - Sealant — Min 5/8 in. (16 mm) thickness of fill material installed to completely fill annular space between pipes

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Reproduced by HILTI, Inc. Courtesy of

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — Hilti CP 606 Flexible Firestop Sealant or FS-ONE Sealant, FS-ONE MAX

conduits and gypsum flush with each surface of wall. Min 1/2 in. (13 mm) diam bead of fill material applied to the through penetrant/wall interface

the individual U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following

A Studs — Wall framing shall consist of min 3-5/8 in. (92 mm) wide steel studs spaced max 24 in. (610 mm) OC.

B. Conduit — Nom 2 in. (51 mm) diam (or smaller) rigid steel conduit or steel electrical metallic tubing (EMT).

The hourly F, FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed

at the point contact locations on both sides of the wall. The 2 hour F, FH Ratings apply only when FS-ONE Sealant is used.


opening is 3-1/2 in. (89 mm). Max width of opening is 32 in. (813 mm).

assembly. The following types and sizes of metallic pipes or conduits may be used:

A. Steel Pipe — Nom 2 in. (51 mm) diam (or smaller) Schedule 5 (or heavier) steel pipe.

CAN/ULC S115

H Ratings - 1 and 2 Hr (See Items 1 and



System No. W-L-2078 F Ratings — 1 and 2 Hr (See Item 1)

T Ratings - 0, 1 and 2 Hr (See Items 2 and 3) L Rating At Ambient — 3 CFM/sq ft

L Rating At 400 F — Less Than 1 CFM/sq ft

. Wall Assembly — The fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in the ndividual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL fire Resistance Directory and shall include the construction

lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.

The hourly F Rating of the firestop system is equal to the hourly fire rating of the wall assembly in which it is installed.

assembly. The following types and sizes of nonmetallic pipes may be used:

(process or supply) or vented (drain, waste or vent) piping system.

supply) or vented (drain, waste or vent) piping system

(drain, waste or vent) piping system

in closed (process or supply) or vented (drain, waste or vent) piping systems

round, rectangular or irregular with a max diam or dimension of 1 in. (25 mm).

A. Max 3/C No. 8 AWG NM copper conductor cable (Romex) with PVC insulation and jacket.

B. Max 7/C-No. 12 AWG copper conductor control cable with PVC or XLPE insulation and jacket.

F. Max 24 fiber optic cable with polyvinyl chloride (PVC) or polyethylene (PE) jacket and insulation

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CFS-D 1" Firestop Cable Disc

H. Maximum 3/C No. 10 AWG copper conductor metal-clad cable

A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm)

Through-Penetrants — One nonmetallic pipe, conduit or tubing to be installed within the firestop system. The annular space between pipe and

periphery of opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Pipe or conduit to be rigidly supported on both sides of the wall

B Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 10 in (254 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or

A. Polyvinyl Chloride (PVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) Schedule 40 solid-core or cellular core PVC pipe for use in closed

. Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use

D. Flame Retardant Polypropylene (FRPP) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or

E. Polyvinylidene Fluoride (PVDF) Pipe — Nom 4 in. (102 mm) diam (or smaller) PVDF pipe for use in closed (process or supply) or vented

When max 6 in. diam pipe is used, T Rating is equal to the hourly fire rating of the wall. When nom 8 in. or 10 in. (203 or 254 mm) diam pipe is

eproduced by HILTI, Inc. Courtesy of

Jnderwriters Laboratories, Inc. January 28, 2015

System No. W-L-3414

. Wall Assembly — The 1 or 2 hr fire rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified

A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 in, (51 mm) by 4 in, (102

in the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the

mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.

B. Gypsum Board\* — 5/8 in. (16 mm) thick, 4 ft (1219 cm) wide with square or tappered edges. The gypsum wallboard type, thickness,

The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

visual fill of min 0% to max 100%. The annular space between the cable bundle and the periphery of the opening to be min 0 in. (point

. Cables — Single or tight bundle of cables to be installed within the opening. Aggregate cross-sectional area of cables in opening to have a

C. Max 100 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with PVC or plenum rated insulation and jacketin D. Max 4 pr No. 22 AWG (or smaller) Cat 5 or Cat 6 computer cables with PVC or plenum rated insulation and jacketing.

. Type RG/U coaxial cable with fluorinated ethylene or PVC insulation and jacketing having a max outside diameter of ½ in. (13 mm).

G. Through Penetrating Product\* — Max two copper conductor No. 18 AWG (or smaller) Power or Non-Power Limited Fire Alarm Cable with

The hourly T, FT and FTH Ratings of the firestop system are dependent on cable type and hourly wall rating as specified in Table below.

s. Fill. Void or Cavity Material\* — Nom 60 mm diam by 3 mm thick putty disc with one seam at radius. Paper-backer of disc to be remoyed and dis


firmly pressed around the cable/cable bundle lapping nom 5 mm onto cables to completely cover opening and firmly pressed to lap onto the wall


ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),


contact). Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types and sizes of cables may be

number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Opening may be


. Gypsum Board\* — Nom 5/8 in. (16 mm) thick gypsum board, as specified in the individual Wall and Partition Design. Max diam of openin







1. Wall Assembly — The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC. B. Gypsum Board\* — 5/8 in. (16 mm) thick, 4 ft (122 cm) wide with square or tapered edges. The gypsum wallboard type, thickness, number o layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 3-1/2 in. 2. Metallic Sleeve Optional — Nom 3-1/2 in. (89 mm) (or smaller) cylindrical sleeve fabricated from min 0.016 in. thick (28 gauge) galv sheet steel and having a min 1-1/4 in. (32 mm) lap salong longitudinal seam. Length of sleeve to be installed flush with wall surfaces. t. Through Penetrants — One nonmetallic pipe installed within the firestop system.. Pipe may be installed at an angle not greater than 45 degrees from perpendicular. Pipe to be rigidly supported on both sides of wall assembly. The space between pipe and periphery of opening shall be min 1/4 in (6 mm) to max 11/16 in (17.5 mm). The following types and sizes of nonmetallic pipes may be used: A. Polyvinyl Chloride (PVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 PVC pipe for use in closed (process or supply) or vented B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems. 4. Fill, Void or Cavity Materials\* — Sealant — For 1 hr F Rating, min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. For 2 hr F Rating, min 1-1/4 in, (32 mm) thickness of fill material applied within annulus, flush with both surfaces of wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant



System No. W-L-2078

Wall Assembly — The 1 or 2 hr fire rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC. B. Gypsum Board\* — 5/8 in. (16 mm) thick, 4 ft (1.22 m) wide with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 7-1/2 in The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed Through Penetrants — One metallic pipe or tubing to be centered within the firestop system. Pipe or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of metallic pipes or tubing may be used: A. Steel Pipe - Nom 4 in. (102 mm) diam (or smaller) Schedule 40 (or heavier) steel pipe B. Copper Tubing — Nom 2 in. (51 mm) diam (or smaller) Type L (or heavier) copper tubing. C. Copper Pipe — Nom 2 in. (51 mm) diam (or smaller) Regular (or heavier) copper pipe.

System No. W-L-7155

2A1. Through-Pentrating Product\* — As an alterate to Item 2. Fiber cement with galvanized steel facing, 3/8 in.(10 mm) thick composite metallic

concentrically or eccentrically within the firestop system such that the annular space is min 0 in. (point contact) to max 2 in. (51 mm). Duct to be

duct, with a max cross-sectional area of 43.0 sq ft, (4 m2) and a max individual dimension of 78 3/4 in. (2 m). Duct to be installed either

2A2. Through-Pentrating Product\* — As an alternate to Item 2. Fiber cement with galvanized steel facing, 1/4 in, (6 mm) thick, with a max

eccentrically within the firestop system such that the annular space is min 0 in. (point contact) to max 2 in. (51 mm). Duct to be rigidly

cross-sectional area of 1764 sq in. (1.14 m2), and a max individual dimension of 42 in. (1067 mm). Duct to be installed either concentrically o

supported on both sides of wall assembly and installed in accordance. Refer to Ventilation Duct Assemblies in Vol. 2 of the Fire Resistance

A3. Through-Pentrating Product\* — As an alternate to Item 2. Galvanized steel faced duct panel, with a max cross-sectional area of 2450 sq in

(1.58 m2), and a max individual dimension of 49-1/2 in. (1258 mm) Duct to be installed either concentrically or eccentrically within the firestop

A. Packing Material — (Optional, Not Shown) — Polyethylene backer rod, mineral wool batt insulation or fiberglass batt insulation friction

fitted into annular space. Packing material to be recessed from both surfaces of wall to accommodate the required thickness of fill material. A1. Packing Material — Required as specified in Table below. Min 3-3/4 in. (95 mm) or 5 in. (127 mm) thickness of min 4 pcf (64 kg/m3)

B. Fill, Void or Cavity Material\* — Sealant — Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. Min 1/4 in. (6 mm) diam bead of fill material shall be applied at the point contact location between the steel duct and the gypsun

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CFS-S SIL GG Sealant, FS-ONE Sealant, FS-ONE MAX Intumescent Sealant

C. Steel Retaining Angles — Min No. 16 gauge galv steel angles sized to lap steel duct a min of 2 in. (51 mm) and to lap wall surfaces a min

of 1 in. (25 mm). When max duct dimension does not exceed 48 in. (122 cm) and duct area does not exceed 1300 in2 (8387 cm2), angles

may be min No. 18 gauge galv steel. Angles attached to steel duct on both sides of wall with min No. 10 by 1/2 in. (13 mm) long steel shee

metal screws located a max of 1 in. (25 mm) from each end of steel duct and spaced a max of 6 in. (152 mm) OC. Steel andles are

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada)

Reproduced by HILTI, Inc. Courtesy

optional for those sides of duct that do not exceed the dimension specified in Table below, dependent on packing material, sealant and

Annular Space Material Required

rigidly supported on both sides of wall assembly. Refer to Ventilation Duct Assemblies in Vol. 2 of the Fire Resistance Directory.




DURASYSTEMS BARRIERS INC — Type DuraDuct HP.

DURASYSTEMS BARRIERS INC — Type DuraDuct SD.

DURASYSTEMS BARRIERS INC — Type DuraDuct GNX. Firestop System — The firestop system shall consist of the following:

Refer to Ventilation Duct Assemblies in Vol. 2 of the Fire Resistance Director

to be recessed from both surfaces of wall to accommodate the required thickness of fill material.




eproduced by HILTI, Inc. Courtesy of


. Wall Assembly — The 1 or 2 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified i the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following A, Studs — Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC. Additional framing members shall be used to completely frame around opening. B. Gypsum Board\* — Min 5/8 in. (16 mm) thick, 4 ft (1.2 m) wide with square or tapered edges. The gypsum board type, thickness, number of layers and orientation shall be as specified in the individual Wall and Partition Design, Max size of opening is 210 sq in, (1355 cm2) with a max width of 14-1/2 in. (368 mm) for wood studs. Max size of opening is 76.2 sq ft. (7 m2) with a max width of 105-1/2 in. (2.7 m) for steel The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall in which it is installed. 2. Steel Duct — Max 100 by 100 in. (2.5 by 2.5 m) steel duct to be installed within the framed opening. The duct shall be constructed and reinforced accordance with SMACNA construction standards. Steel duct to be rigidly supported on both sides of wall assembly.

iii dooordanoo		
		-
Hilti Fire	eston S	vsten
	octop o	,

Reproduced by HILTI, Inc. Courtesy of January 27, 2015



eproduced by HILTI, Inc. Courtesy of



Type and thickness of fire-rated construction. If alternate details matching the

field conditions are not available, manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

Refer to the following

a. 07 84 00 Firestopping

d. 22 00 00 Plumbing

f. 26 00 00 Electrical

e. 23 00 00 HVAC

specification.

specifications for firestopping.

b. 07 84 13 Penetration Firestopping

g. 27 05 37 Communication Systems

For Quality Control requirements, refer

to the Quality Control portion of the

2. Details shown are typical details.

Always refer to the listed system detail

for complete system requirements. If

Design requirements, field conditions

and dimensions need to be verified for

compliance with the details, including

Leakage Rating (L-Rating)

Water Rating (W-Rating)

Temperature Rating (T-Rating)

field conditions do not match

requirements of details, approved

alternate details shall be utilized.

but not limited to the following:

**Annular Space** 

Percent Fill

Fire Rating (F-Rating)

c. 07 84 43 Joints Firestopping

## References:

- 2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.
- NFPA 101 Life Safety Code
- NFPA 70 National Electric Code
- All governing local and regional building codes.
- Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of construction being penetrated.
- All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information.
- Warning! Do Not Disturb Through Penetration Firestop
- UL System # \* Product(s) used Hourly Rating (F-Rating)
- **Installation Date**
- Contractor's Name

without notice.

JOB NUMBER: DRAWN: **CHECKED: REVISIONS:** 

> SHEET NAME: **Gypsum-Walls**

SHEET NUMBER

installed in a wood stud/gypsum board assembly, the max area of square, rectangular, or circular opening is 210 sq in. (1355 cm<sup>2</sup>) with max dimension of 14-1/2 in, (368 mm), If the through penetrants are installed in a steel stud/gypsum board assembly, max area of square. rectangular, or circular opening is 240 sq in. (1548 cm<sup>2</sup>) with max dimension of 20 in. (508 mm) wide. The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed eproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. Underwriters Laboratories, Inc. April 26, 2017 Hilti Firestop Systems

Hilti Firestop Systems

See Plastics+ (QMFZ2) category in the Plastics Recognized Component Directory for names of manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used. The annular space between the insulated penetrants and the periphery of the opening shall be min 0 in. (0 mm, point contact) The The T, FT and FTH Ratings are 1-1/2 hour if Item 3B is used. The T, FT and FTH Ratings are 2 hr if Item 3A is used.

**SECTION A-A** 

Wall Assembly — The 1 or 2 hr fire rated wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the

ndividual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following

A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm)

B. Gypsum Board\* — For 1 hr assembly, one layer of min 5/8 in. (16 mm) thick wallboard as required in the individual Wall and Partition Design For 2 hr assembly, two layers of min 5/8 in. (16 mm) thick wallboard as required in the individual Wall and Partition Design. Max diam of

2. Through Penetrant — Galv steel duct to be installed concentrically or eccentrically within the firestop system. The annular space between the

B. Fill, Void or Cavity Material\*—Sealant — Min 5/8 in. (16 mm) and 1-1/4 in. (32 mm) thickness of fill material applied within annulus, flush with both

surfaces of wall assembly for 1 or 2 hr rated walls, respectively. At the point contact location between duct and wallboard, a min 1/2 in. (13 mm)

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP601S Elastomeric Firestop Sealant, FS-ONE Sealant, FS-ONE MAX Intumes

Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Reproduced by HILTI, Inc. Courtesy of

System No. W-L-8079

Through-Penetrant — One or more pipes, conduit or tubes to be installed within the opening. The total number of through-penetrants is

dependent on the size of the opening and the types and sizes of the penetrants. Any combination of the penetrants described below may be

sed provided that the following parameters relative to the annular spaces and the spacing between the through penetrants are maintained.

ne separation between the penetrants shall be min 1 in. (25 mm) to max 20 in. (508mm). The annular space between penetrants and the

periphery of opening shall be min 0 in. (point contact) to max 20 in. (508 mm). Pipes, conduit or tubes to be rigidly supported on both sides o

F. Polyvinyl Chloride (PVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 cellular or solid core PVC pipe for use in closed

B. Pipe Insulation — One or more metallic penetrants (pipe or tubing) may be insulated with the following types of pipe coverings:

G. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 2 in. (51 mm) diam (or smaller) SDR 13.5 CPVC pipe for use in closed (process or

A. Pipe Covering\* — Min 1 in. (25 mm) to max 2 in. (51 mm) thick hollow cylindrical heavy density min 3.5 pcf (56 kg/m³) glass fiber units

iacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing lap tape.

See Pipe and Equipment Covering - Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe

B. Tube Insulation-Plastics+ — Min 1/2 in. (13 mm) to max 3/4 in. (19 mm) thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible

covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and

wall assembly. The following types and sizes of pipes, conduit or tubes may be used.

The T, FT and FTH Ratings are 0 Hr if bare pipe and tubing is used.

a Smoke Developed Index of 50 or less may be used.

Copper Tubing — Nom 3 in. (76 mm) diam (or smaller) Type L (or heavier) copper tube.

ransverse joints secured with metal fasteners or with butt tape supplied with the product.

. Conduit — Nom 3 in. (76 mm) diam (or smaller) electric metallic tubing (EMT) or rigid steel conduit.

B. Copper Pipe — Nom 3 in. (76 mm) diam (or smaller) Regular (or heavier) copper pipe

C. Steel Pipe - Nom 4 in. (102 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe.

Sealant or CP606 Flexible Firestop Sealant

lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced 24 in. (610 mm) OC.

he hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

A. Spiral Wound HVAC Duct - Nom 20 in. (502 mm) diam (or smaller) No. 24 MSG (or heavier) galv steel spriral wound duct

B. Sheet Metal Duct — Nom 12 in. (305 mm) diam (or smaller) No. 28 MSG (or heavier) galv sheet steel duct.

liam bead of sealant shall be applied at the wallboard/duct interface on both surfaces of wall assembly.

opening is 14-1/2 in. (368 mm) for wood stud walls and 21-3/4 in. (552 mm) for steel stud walls.

G. Max 3/4 in. (19 mm) diam copper ground cable with or without PVC jacket. H. Max 1-1/4in. (32 mm) Diam single or multi conductor mineral-insulated copper-clad cable. The T, FT and FTH Ratings are 1/4 hr if cables D, G and H are used. The T, FT and FTH Ratings are 3/4 Hr for any other combination. space between the tubing and the periphery of the opening shall be min 0 in. (point contact) to a max 1 in. (25 mm). Tubing to be rigidly supported on both sides of wall. . Firestop System — The firestop system shall consist of the following: A Packing Material — In 2 hr fire rated wall assemblies, min 4-3/4 in (121 mm) thickness of min 4 pcf (64 kg/m<sup>3</sup>) mineral wool batt the wall to accommodate the required thickness of fill material. 41. Packing Material — Min 1-1/4 in. (32 mm) thickness of min 4 pcf (64 kg/m³) mineral wool batt insulation firmly packed as a backer this packing material is optional. Packing material can be used in combination with the additional framing members. applied at the gypsum board/through penetrant interface on both surfaces of wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC - FS-ONE Sealant or FS-ONE MAX Intumescent Sealan Bearing the UL Listing Mark # Bearing the UL Recognized Component Mark

. Cables — One max 3 in. (76 mm) diam bundle of cables installed within the opening and rigidly supported on both surfaces of wall. The annular space between the tightly-bundled cables and the periphery of the opening shall be min 0 in. (point contact) to max 20 in. (508 mm). The separation between the cable bundle and the other penetrants shall be min 1 in. (25 mm) to max 20 in. (508 mm). Any combination of the A. Max 25 pair No. 24 AWG telephone cable with polyvinyl chloride (PVC) insulation and jacket. B. Max 7/C No. 12 AWG copper conductor power and control cable with PVC or cross-linked polyethylene (XLPE) insulation and PV

C. Multiple fiber optical communication cable jacketed with PVC and having a max outside diam of 1/2 in. (13 mm). D. Max 3/C No. 8 AWG with bare aluminum ground, PVC insulated steel Metal-Clad+ Cable currently Classified under the Through F. Max 3/C (with ground) No. 8 AWG (or smaller) nonmetallic sheathed (Romey) cable with PVC insulation and jacket materials F. RG/U coaxial cable with polyethylene (PE) insulation and polyvinyl chloride (PVC) jacket having a max outside diam of 1/2 in. (13 mm). A. Through Penetrants — (Not shown) - Max six nom 1 in. (25 mm) diam (or smaller) flexible steel conduits to be installed either concentrically or eccentrically within the firestop system. The annular space between the conduits and the periphery of the opening shall be min 0 in. (point contact) to a max 3 in. (76 mm). Conduits to be rigidly supported on both sides of wall. The T. FT and FTH Ratings are 0 Hr if this penetrant is 4B. Through Penetrants — (Not Shown) - Max twelve nom 3/8 in. (10 mm) diam (or smaller) polyvinyl chloride (PVC) pneumatic tubing for use in closed (process or supply) piping systems. Tubing to be installed either concentrically or eccentrically within the firestop system. The annular

insulation firmly packed into opening as a permanent form. In 1 hr fire rated wall assemblies, min 3-1/2 in. (89 mm) thickness of min 4 pcf around the perimeter of opening as a permanent form. When additional framing members are used to frame the opening (see Item 1A), B. Fill. Void or Cavity Material\* — Sealant — Min 5/8 in. (16 mm) thickness of fill material applied within annulus, flush with both surfaces of wall. At the point contact location between through penetrants and gypsum board, a min 1/2 in. (13 mm) diam bead of fill material shall be Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Inderwriters Laboratories, Inc. **Hilti Firestop Systems** 

Page: 3 of 3

**ISSUE DATE: 01-25-2018** For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as classified by Underwriter's Laboratories, Fire Resistance Directory (Volume 1). Current as of November 19, 2017. System details subject to change

Residential - Flat Deck

Page: 2 of 2

Refer to the following specifications for firestopping. a. 07 84 00 Firestopping b. 07 84 13 Penetration Firestopping c. 07 84 43 Joints Firestopping d. 22 00 00 Plumbing e. 23 00 00 HVAC f. 26 00 00 Electrical g. 27 05 37 Communication Systems

For Quality Control requirements, refer to the Quality Control portion of the specification.

- 2. Details shown are typical details. Always refer to the listed system detail for complete system requirements. If field conditions do not match requirements of details, approved alternate details shall be utilized. Design requirements, field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following: Fire Rating (F-Rating)
- Temperature Rating (T-Rating)
- Leakage Rating (L-Rating)
- Water Rating (W-Rating)
- Annular Space Percent Fill

- Type and thickness of fire-rated construction.
- If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.
- References:
- 2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.
- NFPA 101 Life Safety Code
- NFPA 70 National Electric Code
- All governing local and regional building codes.
- 5. Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of construction being penetrated.
- 6. All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information.
- Warning! Do Not Disturb Through Penetration Firestop
- UL System # \* Product(s) used
- Hourly Rating (F-Rating)
- **Installation Date**
- Contractor's Name
- 7. For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as classified by Underwriter's Laboratories, Fire Resistance Directory (Volume 1).

Current as of November 19, 2017. System details subject to change without notice.

JOB NUMBER: DRAWN: CHECKED: **ISSUE DATE: 01-25-2018** 

*α*. ω.

Residential - Flat Deck


**REVISIONS:** 


SHEET NUMBER

SHEET NAME:

Concrete or Masonry-Walls

4.4





1 or 2-Hr. Gypsum Wall Assembly (2-Hr. Shown)	Steel Stud or Wood Stud (Not Shown)  Power Cable  Firestop Box Insert  UL Listed Non-Metallic Outlet Box (Refer to UL Listing) or UL Listed Metallic Outlet Box (Refer to UL Listing)	
APPLICATION:  Hill Provide Date benefits and for matchin for residence interest of great wat assessment when the services of great wat assessment when the services of services is developed and the services that a services of services is developed and the services that is benefit with the last service of control that the basis of form with the services of control that is benefit to the Provinces of Control that is benefit to the Provinces of Control that is benefit to the Provinces of Control that Control Cont		
	Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. December 07, 2016	

OP BOX INSERT	Wall Opening Protective Materials (CLIV, CLIV
x OE of the control o	CP 617 or CFS-P PA Firestop Putty Pads, for use with flush device UL Listed Metallic Outlet Boxes installed w Nonmetallic Outlet Boxes in framed wall assemblies as specified below. When protective material is used on the wall as directed, the horizontal separation between outlet boxes on opposite sides of the wall may be less boxes are not installed back-to-back (unless otherwise indicated). Installation shall comply with the National 1/8 in. thick (CP 617) or min 0.2 in. (CFS-P PA) thick moldable putty pads are to be installed to completely co outlet box (except for the side of the outlet box against the stud) and conduit fittings/connectors and to compl gypsum board in the wall cavity unless otherwise noted below. When CFS-P PA is used, the putty pads may liner intact on the outside of the pad with the exception of any overlaps, in which case the liner is to be remov overlap location. The box composition, max device dimensions, hourly rating, type of stud and type of faceple CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4 by 4 by max 2-1/8 in, flush device UL Listed Metallic Outlet as specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire RCP 617 or CFS-P PA Firestop Putty Pads, for use with max 4-11/16 by 4-11/16 by max 2-1/8 in, or max 4-3/8 device UL Listed Metallic Outlet Boxes installed with steel cover plates for use in 1 hr fire rated V446 gypsum gypsum board/wood stud Wall and Partition Design No. in the Fire Resistance Directory. When U341 wall de sheathed with 5/8 in, gypsum board, and glass or mineral fiber batt insulation shall be installed in stud cavitie design. Boxes may be installed back-to-back.  CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4-11/16 by 4-11/16 by max 2-1/8 in. flush device U installed with steel cover plates for use in 1 and 2 hr fire rated gypsum board wall assemblies framed with studs and constructed of the materials and in the manner specified in the individual U300, U400 or V400 Ser the Fire Resistance Directory.

wallboard assemblies, framed with min 3-1/2 in, deep wood studs and constructed as specified in the individual U300 Series Wall and

Putty pads shall lap min 1/2 in. onto the stud and gypsum board within the stud cavity. Outlet boxes installed with plastic cover plates.

Partition Designs in the Fire Resistance Directory. Outlet box secured to wood stud by means of two nailing tabs supplied with the outlet box.

Reproduced by HILTI, Inc. Courtesy of

Underwriters Laboratories, Inc.

CP 617 or CFS-P PA Firestop Putty Pads, for use with flush device UL Listed Metallic Outlet Boxes installed with steel mud rings or UL Listed Normetallic Outlet Boxes in framed wall assemblies as specified below. When protective material is used on outlet boxes on both sides of the wall as directed, the horizontal separation between outlet boxes on opposite sides of the wall may be less than 24 in. provided that the boxes are not installed back-to-back (unless otherwise indicated), Installation shall comply with the National Electrical Code (NFPA 70). Min 1/8 in, thick (CP 617) or min 0.2 in. (CFS-P PA) thick moldable putty pads are to be installed to completely ever the exterior surfaces of the outlet box (except for the side of the outlet box against the stud) and conduit fittings/connectors and to completely seal against the stud and gypsum board in the wall cavity unless otherwise noted below. When CFS-P PA is used, the putty pads may be installed with the release liner intact on the outside of the pad with the exception of any overlaps, in which case the liner is to be removed from the bottom layer at the overlap location. The box composition, max device dimensions, hourly rating, type of stud and type of faceplate are specified below. CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4 by 4 by max 2-1/8 in, flush device UL Listed Metallic Outlet Boxes installed with steel cover plates in 1 and 2 hr. fire rated gypsum walloorard wall assemblies framed with min 3-1/2 in, or max 4-3/8 by 4-7/8 by max 2-1/8 in, flush device UL Listed Metallic Outlet Boxes installed with steel cover plates for use in 1 hr fire rated V446 gypsum board/steel stud or U341 gypsum board/steel back or board, and glass or mineral fiber batt insulation shall be installed in stud cavities in accordance with U341 design. Boxes may be installed back-to-back.  CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4-11/16 by 4-11/16 by max 2-1/8 in. flush device UL Listed Metallic Outlet Boxes installed with steel cover plates fo	CP617 / CFS-P PA / FIRESTOP	the manner specified in the individual U400 and V400 Series Wall and Partition Designs in the Fire Resistance Directory. An additional of putty pad material shall be used to plug the end of each electrical metallic tube or conduit at its connection to the box.  HILTI Firestop Box Insert, for use with flush device UL Listed Metallic Outlet Boxes installed with steel mud rings or UL Listed Nonme Boxes in framed wall assemblies as specified below. When protective material is used on outlet boxes on both sides of the wall as
CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4 by 4 by 2-7/8 in. deep UL Listed Nonmetallic Outlet Boxes manufactured by		cover plates in 2 hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep steel studs and constructed of the mate the manner specified in the individual U400 and V400 Series Wall and Partition Designs in the Fire Resistance Directory. An addition
• • • • • • • • • • • • • • • • • • • •		HILTI Firestop Box Insert, for use with flush device UL Listed Metallic Outlet Boxes installed with steel mud rings or UL Listed Nonme
design. Outlet box secured to steel stud by means of fastening tab supplied with the outlet box. Putty pads shall lap min 1/2 in. onto the stud		Boxes in framed wall assemblies as specified below. When protective material is used on outlet boxes on both sides of the wall as the horizontal separation between outlet boxes on opposite sides of the wall may be less than 24 in. provided that the boxes are no back-to-back (unless otherwise indicated). Installation shall comply with the National Electrical Code (NFPA 70). The box compositions are not back-to-back (unless otherwise indicated). Installation shall comply with the National Electrical Code (NFPA 70). The box compositions are not provided that the provided that the boxes are not back-to-back (unless otherwise indicated). Installation shall comply with the National Electrical Code (NFPA 70). The box compositions are not provided that the provided that the boxes are not back-to-back (unless otherwise indicated). Installation shall comply with the National Electrical Code (NFPA 70).
and gypsum board within the stud cavity. Outlet boxes installed with steel or plastic cover plates. Boxes may be installed back to back. CP 617 Firestop Putty Pads, for use with max 2-1/4 by 3-3/4 by 2-3/4 in. deep UL Listed Nonmetallia Outlet Boxes manufactured by Pass and States has each beginning at the street of the plant o		device dimensions, hourly rating, type of stud and type of faceplate are specified below.
Seymore, Inc., and bearing a 2 hr rating under the "Outlet Boxes and Fittings Classification for Fire Resistance" category in the Fire Resistance Directory. Putty pads and boxes for use in 1 and 2 hr fire rated gypsum wallboard assemblies, framed with min 3-1/2 in. deep wood studs and constructed as specified in the individual U300 Series Wall and Partition Designs in the Fire Resistance Directory. Outlet		HILTI Firestop Box Insert, for use with max 4-11/16 by 4-11/16 by 2-1/8 in. deep UL Listed Metallic Outlet Boxes without internal dam hr fire rated gypsum wallboard wall assemblies framed with min 3-1/2 in. deep wood or steel studs and constructed of materials and manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. Outlet but
box secured to wood stud by means of two nailing tabs supplied with the outlet box. Putty pads shall lap min 1/2 in. onto the stud and gypsum board within the stud cavity. Outlet boxes installed with steel or plastic cover plates.		fire rated walls may be installed with plastic or steel cover plates. Outlet boxes in 2 hr fire rated walls shall be installed with steel co One 4-3/8 by 4-3/8 in. insert adhered to the interior back wall of the outlet box in accordance with the instructions supplied with the
CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4 by 3-3/4 by 3 in. deep UL Listed Nonmetallic Outlet Boxes manufactured by		Smaller sized inserts may be cut and combined to achieve the 4-3/8 x 4-3/8 in coverage.  HILTI Firestop Box Insert, for use with max 4 by 4 by 1-1/2 in. deep and 2-1/8 in. deep UL Listed Metallic Outlet Boxes without international control of the
Allied Molded Products, Inc., made from fiber reinforced thermoplastic and bearing a 2 hr rating under the "Outlet Boxes and Fittings Classification for Fire Resistance" category in the Fire Resistance Directory. Putty pads and boxes for use in 1 hr fire rated gypsum		1 or 2 hr fire rated gypsum wallboard wall assemblies framed with min 3 1/2 in . deep steel or wood studs and constructed of materia the manner specified in the individual 1/400. V400 or 1/300 Series Wall and Partition Designs in the Fire Resistance Directory, as si

back to back with 5 in. by 4 in. UL Classified fire block, CP 657 or CFS-BL Firestop Block installed in the cavity between the two boxes.  CP 617 or CFS-P A Firestop Putty Pads, for use with max 14 by 4 by max 2-1/2 in. flush device UL Listed Metallic Outlet Boxes installed with	CFS-P	4 x 4 x 1-1/2 in deep Metallic w/ plastic cover plates 1-hour U300 - wood studs	
steel cover plates in 1 and 2 hr. fire rated gypsum board wall assemblies framed with min 5-1/2 in. deep wood or steel studs for 2 hr fire rated walls and min 3-1/2 in. deep wood or steel studs for 1 hr fire rated walls. Walls constructed as specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. Stud cavity insulation is required and shall consist of min 5-1/2 in. (2 hr rated walls) or min 3-1/2 in. (1 hr rated walls) thick fiberglass (min 0.8 pcf) or mineral fiber (min 4 pcf). Putty pads shall lap min 1/2 in. onto the stud and gypsum board within the stud cavity. When boxes are interconnected by means of electrical metallic tube (EMT) or conduit, a ball of putty pad material shall be used to completely plug the open end of each EMT or conduit within the box.  CP 617 or CFS-P PA Firestop Putty Pads, for use with max 4-11/16 by 4-11/16 by max 2-1/8 in. flush device UL Listed Metallic Outlet Boxes installed with steel or plastic cover plates for use in 1 and 2 hr fire rated gypsum board wall assemblies framed with min 5-1/2 in. deep steel studs and constructed of the materials and in the manner specified in the individual U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. Putty pads shall lap min 1/2 in. onto the stud and gypsum board within the stud cavity. When boxes are interconnected by means of electrical metallic tube (EMT) or conduit, a ball of putty pad material shall be used to completely plug the open end of each EMT	CP617 /	HILTI Firestop Box Insert, for use with max 2 1/8 x 4 x 2 1/8 in. deep UL Listed Metallic Outlet Boxes without internal clamps in 2 hr firer gypsum wallboard wall assemblies framed with min 3 1/2 in. deep wood or steel studs and constructed of materials and in the manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. Outlet boxes may be installed with steel cover plates. One 1-7/8 x 2-13/16 insert adhered to the interior back wall of the outlet box in accordance with the instructions supplied with the product.  HILTI Firestop Box Insert, for use with max 4-1/2 x 8-1/2 in. by 1-5/8 in. deep or max 3-3/4 x 5-1/2 in. by 2-1/2 in deep UL Listed Metallic Boxes without internal clamps in 1 hr or 2 hr fire rated gypsum wallboard wall assemblies framed with min 3 1/2 in. deep steel or wood and constructed of materials and in the manner specified in the individual U400, V400 or U300 Series Wall and Partition Designs in the Resistance Directory, as summarized in the Table below. Outlet boxes installed with steel cover plates. Box inserts evenly spaced and adhered to the interior back wall of the outlet box in accordance with the instructions supplied with the product.	r be C Outlet d studs e Fire
or conduit within the outlet boxes. Metallic outlet boxes may be provided with steel attachment brackets which offset box min 1/4 in. from stud.		Box Size Inserts Used Fire Rating Wall Type	$\overline{}$
When steel attachment brackets are used, putty pad to be affixed to the back and all four sides of the box.  CFS-P PA Moldable Putty Pads, for use with max 4-11/16 by 4-11/16 in. by max 2-1/8 in. flush device UL Listed Metallic Outlet Boxes installed with steel cover plates in 2 hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep steel studs and constructed of the		4-1/2 x 8-1/2 x 1-5/8 in Two 3-11/16 x 3-3/4 in inserts ** 2 hour U300, U400 or V400 - wo	ood or I studs
materials and in the manner specified in the individual U400 and V400 Series Wall and Partition Designs in the Fire Resistance Directory. An additional 3/4 in. ball of putty pad material shall be used to plug the end of each electrical metallic tube or conduit at its connection to the box. CFS-P PA Moldable Putty Pads, for use with max 4 by 4 by 2-1/8 in. flush device UL Listed Metallic Outlet Boxes installed with steel or plastic			ood or I studs
cover plates in 2 hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep steel studs and constructed of the materials and in the manner specified in the individual U400 and V400 Series Wall and Partition Designs in the Fire Resistance Directory. An additional 3/4 in. ball of putty pad material shall be used to plug the end of each electrical metallic tube or conduit at its connection to the box.		** - Min 3/4 in. deep plaster rings installed over outlet box. After installation of gypsum board, nom 1/4 in. thickness of Hilti FS-ONE Sealant or FS-ONE MAX Intumescent Sealant, bearing the UL Classification Mar for Fill, Void or Cavity Materials, applied between the base layer of wallboard and the plaster ring.	king
cover plates in 2 hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep steel studs and constructed of the materials and in the manner specified in the individual U400 and V400 Series Wall and Partition Designs in the Fire Resistance Directory. An additional 3/4 in. ball of putty pad material shall be used to plug the end of each electrical metallic tube or conduit at its connection to the box.  HILTI Firestop Box Insert, for use with flush device UL Listed Metallic Outlet Boxes installed with steel mud rings or UL Listed Nonmetallic Outlet Boxes in framed wall assemblies as specified below. When protective material is used on outlet boxes on both sides of the wall as directed, the horizontal separation between outlet boxes on opposite sides of the wall may be less than 24 in. provided that the boxes are not installed back-to-back (unless otherwise indicated). Installation shall comply with the National Electrical Code (NFPA 70). The box composition, max device dimensions, hourly rating, type of stud and type of faceplate are specified below.  HILTI Firestop Box Insert, for use with max 4-11/16 by 4-11/16 by 2-1/8 in. deep UL Listed Metallic Outlet Boxes without internal clamps in 1 or 2 hr fire rated gypsum wallboard wall assemblies framed with min 3-1/2 in. deep wood or steel studs and constructed of materials and in the manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory, Outlet boxes in 1 hr fire rated walls may be installed with plastic or steel cover plates. Onte 4-3/8 by 4-3/8 in. insert adhered to the interior back wall of the outlet box in accordance with the instructions supplied with the product. Smaller sized inserts may be cut and combined to achieve the 4-3/8 x 4-3/8 in coverage.  HILTI Firestop Box Insert, for use with max 4 by 4 by 1-1/2 in. deep and 2-1/8 in. deep UL Listed Metallic Outlet Boxes without internal clamps in 1 or 2 hr fire rated gypsum wallboard wall assemblies framed with min 3 1/2 in. deep s		HILTI Firestop Box Insert , for use with 4-3/8 by 4-7/8 by 2-1/4 in. deep flush device UL Listed Metallic Outlet Boxes without internal clar hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep wood or steel studs and constructed of the materials and in manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. One 4-3/8 in by 4-3/8 in. high insert adhered to the interior back wall of the outlet box in accordance with the installation instructions supplied with the product. Smaller sized inserts may be cut and combined to achieve the 4-3/8 in. by 4-3/8 in. coverage and adhered to the interior back the outlet box. Outlet boxes installed with plastic or steel cover plates.  HILTI Firestop Box Insert, for use with 4-3/8 by 4-7/8 by 2-1/4 in. deep flush device UL Listed Metallic Outlet Boxes without internal clam hr fire rated gypsum board wall assemblies framed with min 3-1/2 in. deep wood or steel studs and constructed of the materials and in manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the Fire Resistance Directory. One 4-3/8 in by 4-3/8 in. high insert adhered to the interior back wall of the outlet box in accordance with the installation instructions supplied with troduct. Smaller sized inserts may be cut and combined to achieve the 4-3/8 in. by 4-3/8 in. coverage and adhered to the interior back the outlet box. Outlet boxes installed with steel cover plates.  CP 617 or CFS-P PA Firestop Putty Pads and HILTI Firestop Box Inserts, for use with maximum 4 by 4 by 1-1/2 in. (102 by 102 by 38 m flush device UL Listed Metallic Outlet Boxes installed with steel mud rings and with steel or plastic faceplates in 1 or 2 hr fire rated gyp board wall assemblies constructed with min 3-1/2 in. (89 mm) wide wood or steel studs. When both protective materials are used with boxes on both sides of the wall as directed, the boxes may be installed back-to-back provided that the backs of the boxes are m	the in. wide he k wall of mps in 2 in wide he in. wide he k wall of mps in 2 in. wide he k wall of mm) deep osum outlet m 1/2 in.
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. December 07, 2016		Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. December 07, 2016	
Hilti Firestop Systems Page: 4 (	of 5	Hilti Firestop Systems	Page: 5 d

Wall Opening Protective Materials (CLIV, CLIV7)

Box Size	Type of Box and Cover Plate	Hourly Rating	Wall Type
4 x 4 x 2-1/8 in deep	Metallic w/ steel cover plates	2-hour	U300, U400 or V400 - wood or steel studs
1 x 4 x 2-1/8 in deep	Metallic w/ plastic cover plates	1-hour	U300, U400 or V400 - wood or steel studs
l x 4 x 1-1/2 in leep	Metallic w/ plastic cover plates	1-hour	U300 - wood studs

Box Size	Inserts Used	Fire Rating	Wall Type		
4-1/2 x 8-1/2 x 1-5/8 in deep	Two 3-11/16 x 3-3/4 in. inserts **	2 hour	U300, U400 or V400 - wood or steel studs		
-3/4 x 5-1/2 x 2-1/2 in One 3-11/16 x 3-3/4 in. insert and eep one 1-7/8 x 2-13/16 in. insert		1 hour	U300, U400, or V400 - wood or steel studs		
**- Alin 3/4 in. deep plaster rings installed over outlet box. After installation of gypsum board, nom 1/4 in. hickness of Hilti FS-ONE Sealant or FS-ONE MAX Intumescent Sealant, bearing the UL Classification Marking for Fill, Void or Cavity Materials, applied between the base layer of wallboard and the plaster ring.					

Refer to the following specifications for firestopping. a. 07 84 00 Firestopping b. 07 84 13 Penetration Firestopping c. 07 84 43 Joints Firestopping d. 22 00 00 Plumbing e. 23 00 00 HVAC f. 26 00 00 Electrical g. 27 05 37 Communication Systems

For Quality Control requirements, refer to the Quality Control portion of the specification.

- 2. Details shown are typical details. Always refer to the listed system detail for complete system requirements. If field conditions do not match requirements of details, approved alternate details shall be utilized. Design requirements, field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following:
- Fire Rating (F-Rating) Temperature Rating (T-Rating)
- Leakage Rating (L-Rating)
- Water Rating (W-Rating) **Annular Space**
- Percent Fill
- Type and thickness of fire-rated construction.
- If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable subject to approval by the Authority Having Jurisdiction (AHJ). Contact Hilti Inc. for alternative systems or Engineering Judgment (800-879-8000). Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.
- References:
- 2017 Underwriter's Laboratories Fire Resistance Directory, Volumes 1 & 2.
- NFPA 101 Life Safety Code
- NFPA 70 National Electric Code
- All governing local and regional building codes.
- 5. Firestop System installation must meet requirements of ASTM E-814 (UL 1479) tested assemblies that provide a fire rating equal or greater to that of construction being penetrated.
- 6. All rated through-penetration assemblies shall be prominently labeled with a Hilti Firestop Label equipped with a QR code with the following information.
- Warning! Do Not Disturb Through Penetration Firestop
- UL System # \* Product(s) used
- Hourly Rating (F-Rating)
- **Installation Date** Contractor's Name
- 7. For outlet boxes requiring protection, use only Wall Opening Protective Materials, category CLIV as classified by Underwriter's Laboratories, Fire Resistance Directory (Volume 1).

Current as of November 19, 2017. System details subject to change without notice.

JOB NUMBER: DRAWN: CHECKED: **ISSUE DATE: 01-25-2018 REVISIONS:** 


*α*. ω.

SHEET NUMBER

Residential - Flat Deck **Membrane-Penetration** 


SHEET NAME:

4.5



in the individual U400, V400 or W400 Series Wall or Partition Design in the UL Fire Resistance Directory. In addition, the wall may incorporate a head-of-wall joint system as specified in the HW Series Joint Systems in the UL Fire Resistance Directory. The wall shall include the following A. Steel Floor Runners — Floor runners of wall assembly shall consist of min No. 25 gauge galv steel channels sized to accommodate steel studs (Item 2B). Floor runners to be provided with 1-1/4 in. (32 mm) flanges. Runners secured with steel fasteners spaced 12 in. (305 mm) B. Studs — Steel studs to be min 3-1/2 in. (89 mm) wide. Studs cut 1/2 to 3/4 in. (13 to 19 mm) less in length than assembly height with bottom nesting in, resting on and fastened to floor runner with sheet metal screws. Stud spacing not to exceed 24 in. (610 mm) OC. Gypsum Board\* — Gypsum board installed to a min total thickness of 5/8 or 1-1/4 in. (16 or 32 mm) on each side of wall for a 1 or 2 hr rated wall, respectively. Wall to be constructed as specified in the individual U400, V400 or W400 Series Design in the UL Fire Resistance Directory except that a max 3/4 in. (19 mm) gap shall be maintained between the bottom of gypsum board and top of concrete floor. The hourly fire rating of the joint system is equal to the hourly fire rating of the wall.

Fill, Void or Cavity Material\* Sealant — Max separation between top of floor and bottom of gypsum board wall sheathing is 3/4 in. (19 mm). Min 5/8 in. (16 mm) thickness of fill material installed on each side of the wall between the bottom of the gypsum board and the top of the concrete floor, flush with each surface of the wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 605 Bottom of Wall Firestop Sealant, CP601S Elastomeric Firestop Sealant, CP606 Flexible Firestop Sealant, CFS-S SIL GG, FS-ONE Sealant or FS-ONE MAX Intumescent Sealant Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),



Floor Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete. Floor may also be constructed of any 6 in. (152 mm) thick UL Classified hollow-core Precast Concrete Units\* See Precast Concrete Units category in the Fire Resistance Directory for names of manufactures. . Wall Assembly — The 1 or 2 h fire-rated gypsum board/steel stud wall assembly shall be constructed of the materials and in the manner specified in the individual U400, V400 or W400 Series Wall or Partition Design in the UL Fire Resistance Directory. In addition, the wall may incorporate a head-of-wall joint system as specified in the HW Series Joint Systems in the UL Fire Resistance Directory. The wall shall include the following A. Steel Floor Runners — Floor runners of wall assembly shall consist of min No. 25 gauge galv steel channels sized to accommodate steel studs (Item 2B). Floor runners to be provided with 1-1/4 in. (32 mm) flanges. Runners secured with steel fasteners spaced 12 in. (305 mm) OC 3. Studs — Steel studs to be min 3-1/2 in. (89 mm) wide. Studs cut 1/2 to 3/4 in. (13 to 19 mm) less in length than assembly height with bottom nesting in, resting on and fastened to floor runner with sheet metal screws. Stud spacing not to exceed 24 in. (610 mm) OC. C. Gypsum Board\* — Gypsum board installed to a min total thickness of 5/8 or 1-1/4 in, (16 or 32 mm) on each side of wall for a 1 or 2 hr rated

wall, respectively. Wall to be constructed as specified in the individual U400, V400 or W400 Series Design in the UL Fire Resistance Director except that a max 3/4 in. (19 mm) gap shall be maintained between the bottom of gypsum board and top of concrete floor. The hourly fire rating of the joint system is equal to the hourly fire rating of the wall. Fill, Void or Cavity Material\* — Bottom Track Seal — Max separation between the bottom of floor and bottom of wall is 3/4 in. (19 mm). Factory supplied foam seal installed under the floor runners (Item 2A) prior to attachment to top side of concrete floor in accordance with the installation HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CFS-TTS 358, CFS-TTS 600 or CFS-TTS-OS Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

System No. HW-D-0757


Floor Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete

2. Wall Assembly — The 1 or 2 h fire-rated gypsum board /steel stud wall assembly shall be constructed of the materials and in the manner

Reproduced by HILTI, Inc. Courtesy of

Floor may also be constructed of any 6 in. (152 mm) thick UL Classified hollow-core Precast Concrete Units\*.

See Precast Concrete Units category in the Fire Resistance Directory for names of manufactures.



. Floor Assembly — Min 4-1/2 in. (114 mm) thick steel-reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete Floor may also be constructed of any 6 in. (152 mm) thick UL Classified hollow-core Precast Concrete Units\* 2. Wall Assembly — The 1 or 2 hr fire-rated gypsum board /stud wall assembly shall be constructed of the materials and in the manner specified in the individual U400 or V400 Series Wall and Partition Design in the UL Fire Resistance Directory and shall include the following construction features A. Steel Floor and Ceiling Runners — Floor and ceiling runners of wall assembly shall consist of min No. 25 gauge galv steel channels sized to accommodate steel studs (Item 2B). Flange height of ceiling runner shall be min 1/4 in. (6 mm) greater than max extended joint width. Ceiling runner secured to concrete floor slab with steel masonry anchors or steel fasteners spaced 24 in. (610 mm) OC. A1. Light Gauge Framing\*-Slotted Ceiling Runner — (For use in applications where the nominal joint width does not exceed 1-1/2 in. or 38 mm) As an alternate to the ceiling runner in Item 2A, slotted ceiling runner to consist of galv steel channel with slotted flanges sized to accommodate

steel studs (Item 2B). Slotted ceiling runner secured to concrete floor slab with steel masonry anchors or steel fasteners spaced max 24 in. (610 BRADY CONSTRUCTION INNOVATIONS INC, DBA SLIPTRACK SYSTEMS — SLP-TRK CALIFORNIA EXPANDED METAL PRODUCTS CO — CST CLARKDIETRICH BUILDING SYSTEMS — Type SLT, SLT-H MARINO/WARE, DIV OF WARE INDUSTRIES INC — Type SLT METAL-LITE INC — The System SCAFCO STEEL STUD MANUFACTURING CO TELLING INDUSTRIES L L C — True-Action Deflection Track

Reproduced by HILTI, Inc. Courtesy of

System No. HW-D-0209 L Rating At Ambient — Less Than 1 CFM/sq ft (See Item FTH Ratings - 1 and 2 Hr (See Item 2 . Rating At 400 F — Less Than 1 CFM/sq ft (See Item 3) Nominal Joint Width - 1 L Rating At Ambient — Less Than 1 CFM/sq ft (See Item L Rating At 400 F — Less Than 1 CFM/sq ft (See Item 3 I. Floor Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete Floor may also be constructed of any 6 in. (152 mm) thick UL Classified hollow-core Precast Concrete Units\*. See Precast Concrete Units category in the Fire Resistance Directory for names of manufactures. 2. Wall Assembly — The 1 or 2 h fire rated gypsum board/steel stud wall assembly shall be constructed of the materials and in the manner specified in the individual U400, V400 or W400 Series Wall and Partition Design in the UL Fire Resistance Directory and shall include the following A. Steel Floor and Ceiling Runners — Floor and ceiling runners of wall assembly shall consist of min No. 25 gauge galv steel channels sized to accommodate steel studs (Item 2B). Flange height of ceiling runner shall be min 1/4 in. (6 mm) greater than max extended joint width. Ceiling runner secured with masonry anchors or steel fasteners spaced 24 in. (610 mm) OC.

System No. HW-D-0106

A2 . Light Gauge Framing\*-Vertical Deflection Ceiling Runner — (For use in applications where the nominal joint width does not exceed 1 in.

or 25 mm) - As an alternate to the ceiling runners in Items 2A and 2A1, vertical deflection ceiling runner to consist of galv steel channel with

slotted vertical deflection clips mechanically fastened within runner. Slotted clips provided with step bushings for permanent fastening of

steel studs. Flanges sized to accommodate steel studs (Item 2B). Vertical deflection ceiling runner masonry anchors or steel fasteners with

A3. Light Gauge Framing\*- Notched Ceiling Runner — As an alternate to the ceiling runners in Items 2A through 2A3, notched ceiling runners

to consist of C-shaped galv steel channel with notched return flanges sized to accommodate steel studs (Item 2B). Notched ceiling runner

B. Studs — Steel studs to be min 2-1/2 in. (64 mm) wide. Studs cut 1/2 to 3/4 in. (13 to 19 mm) less in length than assembly height with

bottom nesting in and resting on floor runner and with top nesting in ceiling runner without attachment. When slotted ceiling runner (Item

2A1) is used, steel studs secured to slotted ceiling runner with No. 8 by 1/2 in. (13 mm) long wafer head steel screws at midheight of slot or

each side of wall. When vertical deflection ceiling runner (Item 2A2) is used, steel studs secured to slotted vertical deflection clips, through

C. Gypsum Board\* — Gypsum board installed to a min total thickness of 5/8 or 1-1/4 in. (16 or 32 mm) on each side of wall, for 1 or 2 hr fire

Resistance Directory, except that a nominal 2 in. (51 mm) gap shall be maintained between the top of the gypsum board and the bottom of

concrete floor. The screws attaching the gypsum board to the studs at the top of the first layer shall be located 4 in. (102 mm) from the floor

assembly. The screws attaching the second layer to the steel studs shall be located 3-1/2 in. (89 mm) from the floor assembly. The hourly

Joint System — Max width of joint (at time of installation of joint system) is 2 in. (51 mm). The joint system is designed to accommodate a max

A. Forming Material \* — Nom 5/8 or 1-1/4 in. (16 or 32 mm) thick strips of min 4 pcf (64 kg/m3) mineral wool batt insulation, for 1 and 2 Hr

rated assemblies, respectively, cut to width, compressed 33 percent in width and firmly packed into gap between top of the gypsum board

and bottom of the floor assembly, flush with both surfaces of the wall. Adjoining lengths of batt to be tightly butted with butted seams spaced

A1. Forming Material\* - Strips — (Optional) - Nom 5/8 in. (16 mm) and 1-1/4 in. (32 mm) wide precut mineral wool strips for 1 and 2 hr rated

assemblies, respectively. The strips are cut to thickness, compressed 50 percent in thickness and firmly packed into the gap between the

top of the gypsum board and bottom of the floor assembly, flush with both surfaces of the wall. Adjoining lengths of strips to be tightly butted

B. Fill, Void or Cavity Material\* — Min 1/16 in. (1.6 mm) dry thickness (min 1/8 in. or 3.2 mm wet thickness) of fill material sprayed or troweled

on each side of the wall to completely cover mineral wool forming material and to overlap min 1/2 in. (13 mm) onto the gypsum board and

ndicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

concrete floor assembly.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP672 Firestop Spray or CFS-SP WB Firestop Joint Spray

resistance rated walls, respectively. Wall to be constructed as specified in the individual U400 or V400 Series Design in the UL Fire

steel masonry anchors spaced max 24 in. (610 mm) OC.

OLMAR SUPPLY INC — Type SCR

THE STEEL NETWORK INC — VertiTrack VTD250, VTD362, VTD400, VTD600 and VTD800

fire rating of the joint system is dependent on the hourly rating of the wall.

with butted seams spaced min 48 in. (1.2 m) apart along the length of the joint.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 767 Speed Strips

min 48 in. (1.2 m) apart along the length of the joint.


ROXUL INC — SAFE

THERMAFIBER INC — Type SAF

secured to concrete floor slab with steel masonry anchors or steel fasteners spaced max 24 in. (610 mm) OC.

the bushings, with steel screws at midheight of each slot. Stud spacing not to exceed 24 in. (610 mm)  $\,$  OC  $\,$ 

20 percent compression or extension from its installed width. The joint system shall consist of the following:



Underwriters Laboratories, Inc. February 23, 2015

A1. Light Gauge Framing\* — Slotted Ceiling Runner - As an alternate to the ceiling runner in Item 2A, slotted ceiling runner to consist of galv steel channel with slotted flanges sized to accommodate steel studs (Item 2B). Slotted ceiling runner secured to valleys lower surface of floor with steel fasteners spaced max 24 in. (610 mm) OC. exceed 24 in. (610 mm) OC.

BRADY CONSTRUCTION INNOVATIONS INC, DBA SLIPTRACK SYSTEMS — SLP-TRK CALIFORNIA EXPANDED METAL PRODUCTS CO — CST MARINO/WARE, DIV OF WARE INDUSTRIES INC — Type SLT A2. Light Gauge Framing\* — Vertical Deflection Ceiling Runner - As an alternate to the ceiling runners in Items 2A and 2A1, vertical deflection ceiling runner to consist of galv steel channel with slotted vertical deflection clips mechanically fastened within runner. Slotted clips provided with step bushings for permanent fastening of steel studs. Flanges sized to accommodate steel studs (Item 2B). Vertical deflection ceiling runner secured to lower surface of floor with steel fasteners spaced max 24 in. (610 mm) OC. THE STEEL NETWORK INC — VertiTrack VTD250, VTD362, VTD400, VTD600 and VTD800 B. Studs — Steel studs to be min 3-1/2 in. (89 mm) wide. Studs cut 1/2 to 3/4 in. (13 to 19 mm) less in length than assembly height with bottom nesting in and resting on floor runner and with top nesting in ceiling runner without attachment. When slotted ceiling runner (Item 2A1) is used, steel studs secured to slotted ceiling runner with No. 8 by 1/2 in. (13 mm) long wafer head steel screws at midheight of slot on each side of wall. Stud spacing not to exceed 24 in. (610 mm) OC. When vertical deflection ceiling runner (Item 2A2) is used, steel studs secured to slotted vertical deflection clips, through the bushings, with steel screws at midheight of each slot. Stud spacing not to

C. Gypsum Board\* — For 1 hr assembly, one layer of 5/8 in. (16 mm) thick gypsum board is required in the individual Wall and Partition Design. For 2 hr assembly, two layers of 5/8 in. (16 mm) thick gypsum board is required in the individual Wall and Partition Design. Wall to be constructed as specified in the individual U400 or V400 Series Design in the UL Fire Resistance Directory, except that a max 1 in. (25 mm) gap shall be maintained between the top of gypsum board and bottom of concrete floor. The screws attaching the gypsum board to the studs at the top of the first layer shall be located 4 in. (102 mm) below the floor. The screws attaching the second layer to the steel studs shall be installed into the studs 3-1/2 in. (89 mm) below the floor. The hourly fire rating of the joint system is equal to the hourly ratings of the walls. 3. Fill, Void or Cavity Material\* - Sealant — Max separation between bottom of floor and top of wall is 1 in. (25 mm). The joint system is designed to accommodate a max 19 percent compression or extension from its installed width. Min 5/8 in. (16 mm) thickness of fill material installed on each side of the wall between the top of the gypsum board and the bottom of the concrete floor, flush with each surface of the wall. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP601S Elastomeric Firestop Sealant or CP606 Flexible Firestop Sealant or CFS-S SIL GG Sealant. L Ratings apply only when CP606 or CFS-S SIL GG Sealant is used. 4. Forming Material — (Optional, Not Shown) - Mineral wool insulation, fiberglass batt insulation or polyurethane/polyethylene foam backer rod. Forming material to be recessed from both surfaces of the 2 hr fire rated wall to accommodate the required thickness of fill material. Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada),

Refer to section 07840 of the specifications. For Quality Control requirements, refer to

the Quality Control portion of the specification. Details shown are typical details. If field conditions do not match requirements of typical details, approved alternate details shall be utilized. Field conditions and dimensions need

to be verified for compliance with the details, including but not limited to the following: Minimum and maximum Width of Joints

Type and thickness of fire-rated construction. The minimum assembly rating of the firestop assembly shall meet or exceed the highest rating of the adjacent construction.

If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable. Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

References:


Page: 2 of 2

2017 Underwriter's Laboratories Fire Resistance Directory, Volume 2

Intertek Directory of Building Products

All governing local and regional building codes

Current as of November 19, 2017. System details subject to change without notice.






JOB NUMBER: **DRAWN**: **CHECKED: ISSUE DATE: 01-25-2018** 

SHEET NAME: Residential - Flat Deck Joints-Gypsum-Walls


SHEET NUMBER

**REVISIONS:** 



2. Shaft Wall Assembly — The 2 hr fire-rated gypsum board /steel stud shaft wall assembly shall be constructed of the materials and in the manner described in the individual U400, V400 or W400 Series Wall and Partition Design in the UL Fire Resistance Directory and shall include the following construction features: A. Floor and Ceiling Runners — J-shaped runner, 2-1/2 in. (64 mm) wide with unequal legs of min 1-1/4 in. (32 mm) and 2 in. (51 mm), fabricated from min 24 MSG galv steel. Runners positioned with short leg toward finished side of wall. Runners attached to structural supports with steel fasteners located not greater than 2 in. (51 mm) from ends and not greater than 24 in. (610 mm) OC. B. Light Gauge Framing\* - Slotted Ceiling Track — (Optional) Slotted ceiling track shall consist of galv steel channels with slotted flanges. Slotted ceiling track sized to accommodate steel "C-H" studs (Items 2C). Attached to concrete at ceiling with steel fasteners spaced max 24 CALIFORNIA EXPANDED METAL PRODUCTS CO — CST BRADY CONSTRUCTION INNOVATIONS INC. DBA SLIPTRACK SYSTEMS — SLP-TRK MARINO/WARE, DIV OF WARE INDUSTRIES INC — Type SLT B1. Light Gauge Framing Members\* — (Optional Not Shown) - As an option, the steel studs (Item 2C) may incorporate vertical deflection clips for attachment to the ceiling runner (Item 2A) in accordance with the manufacturer's instructions THE STEEL NETWORK INC — VertiClip SLD 150. C. Steel Studs — C-H-shaped studs, 2-1/2 in. (64 mm) wide by 1-1/2 in. (38 mm) deep, fabricated from min 25 MSG galv steel, cut to lengths 3/8 to 1/2 in. (10 to 13 mm) less than floor to ceiling height and spaced 24 in. (610 mm) OC. Studs nest in floor runner at bottom and J runner or slotted ceiling track at top. After installation of gypsum board liner panels (Item 2D), studs secured to flange of floor runner on finished side of wall only with No. 6 by 1/2 in. (13 mm) long self-drilling, self-tapping steel screws. Studs secured to flange of slotted ceiling track on finished side of wall only with No. 8 by 1/2 in. (13 mm) long self-drilling, self-tapping wafer head steel screws at slot midheight. D. Gypsum Board\* — 1 in. (25 mm) thick by 24 in. (610 mm) wide gypsum board liner panels as specified in the individual U400 or V400-Series design. Panels cut 1 in. (25 mm) less in length than floor to ceiling height. Vertical edges inserted in "H"-shaped section of 1-5/8 in. (41 mm) long Type S steel screws spaced max 12 in. (305 mm) OC.

E. Gypsum Board\* — Gypsum board sheets, 1/2 or 5/8 in. (13 or 16 mm) thick, applied vertically or horizontally in two layers on finished side of wall as specified in the individual U400 or V400-Series design. A max 1 in. (25 mm) gap shall be maintained between the top of the gypsum board and the bottom surface of the concrete floor. The screws attaching the gypsum board layers to the C-H studs shall be located 1 in. (25 mm) below the bottom of the J-runner or slotted ceiling track. No gypsum board attachment screws are to penetrate the ceiling Joint System — Max separation between top of liner panel (Item 2D) and between top of gypsum board sheets (Item 2E) at time of installation of joint system is 1 in. (25 mm). The joint system is designed to accommodate a maximum 8 percent compression and extension from its installed width. The joint system consists of the following: A. Fill, Void or Cavity Material\* - Sealant — Min 1 in. (25 mm) depth of sealant to be installed to fill linear gap between top of gypsum board liner panel (Item 2D) and top inside surface of ceiling J-runner or slotted ceiling track prior to installation of gypsum board (ItemD2E) on finished side of wall. Min 1 in. (25 mm) depth of sealant to be installed to fill linear gap between top of gypsum board sheets (Item 2E) and HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 606 \*Bearing the UL Classification Mark



System No. HW-D-0572 System No. HW-D-0572 ANSI/UL2079 CAN/ULC S115 B1. Light Gauge Framing\* - Slotted Ceiling Runner — As an alternate to the ceiling runner in Item 2B, slotted ceiling runner to consist of galv steel channel with slotted flanges sized to accommodate steel studs (Item 2C). Flange height of slotted ceiling runner shall be min 1/4 in. (6 and spaced max 24 in. (610 mm) OC.
BRADY CONSTRUCTION INNOVATIONS INC, DBA SLIPTRACK SYSTEMS — SLP-TRK CALIFORNIA EXPANDED METAL PRODUCTS CO — CST CLARKDIETRICH BUILDING SYSTEMS — Type SLT, SLT-H MARINO/WARE, DIV OF WARE INDUSTRIES INC — Type SLT METAL-LITE INC — The System SCAFCO STEEL STUD MANUFACTURING CO — Slotted Track TELLING INDUSTRIES L L C — True-Action Deflection Track
C. Steel Studs — C-H shaped studs, min 4 in. (102 mm) wide by 1-1/2 in. (38 mm) deep, fabricated from 25 MSG galv steel, cut to lengths 3/4 to 1 in. (19 to 25 mm) less than floor to ceiling height and spaced 24 in. (610 mm) OC. D. Gypsum Board\* — Nom 1 in. (25 mm) thick gypsum board liner panels. Panels cut 1-1/2 in. (38 mm) less in length than floor to ceiling height. Vertical edges inserted in H-shaped section of C-H studs. At the ends of the assembly, the free edge of the end panels are attached to the long leg of vertical J-runners (Item 2A) with 1-5/8 in. (41 mm) long Type S steel screws spaced max 12 in. (305 mm) OC. E. Gypsum Board\* — Nom 5/8 in. (16 mm) thick gypsum board applied vertically in one or two layers for 1 hr and 2 hr fire rated assemblies, respectively. Panels cut 1-1/2 in. (38 mm) less in length than floor to ceiling height. The screws attaching the gypsum board layers to the C-H studs shall be located 1 to 1-1/2 in. (25 to 38 mm) below the bottom of the ceiling runner or slotted ceiling track. No gypsum board attachment screws are to penetrate the ceiling runner or slotted ceiling track.

The hourly ratings of the joint system are equal to the hourly fire rating of the wall. . Joint System — Max separation between bottom of floor and top of gypsum board (at the time of installation of the joint system) is 1 1/2 in. (38 mm). The joint system is designed to accommodate a max 50 percent compression or extension from its installed width. The joint system consis A. Forming Material\* — Min 4 pcf (64 kg/m3) density mineral wool batt insulation cut to a thickness twice larger than the distance between the top of the gypsum board and the bottom of the floor. Material compressed 50 percent and installed within ceiling runner above top of liner panel flush with the inside surface of the panel. Material compressed and installed on finished side of the wall between the top of the gypsum board and the bottom of the floor, flush with the surface of the wall. ROXUL INC — SAFE THERMAFIBER INC — Type SAF 1. Forming Material\* - Strips — As an alternate to Item 2A, the strips are stacked to a height twice larger than the distance between the top of the gypsum board and the bottom of the floor. Strips compressed 50 percent and installed within ceiling runner above top of liner panel flush with the inside surface of the panel. Strips compressed and installed on finished side of the wall between the top of the gypsum board and the HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 767 Speed Strips B. Fill. Void or Cavity Material\* — Min 1/16 in. (1.6 mm) dry thickness (1/8 in. or 3.2 mm wet thickness) of fill material sprayed or troweled within stud cavity and on finished side of the shaft wall to completely cover mineral wool forming material. Fill material to overlap a min of 1/2 in. (13 mm) onto gypsum board and ceiling runner within stud cavity. Fill material to overlap a min of 1/2 in. (13 mm) onto gypsum board and HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 672 Firestop Spray or CFS-SP WB Firestop Joint Spray Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), B. Ceiling Runner — Ceiling runner shall consist of galv steel channel sized to accommodate steel studs (Item 2C). Flange height of ceiling runner shall be min 1/4 in. (6 mm) greater than max extended joint width. Ceiling runner secured with steel fasteners located not more than 2 in. (51 mm) from ends and spaced not greater than 24 in. (610 mm) OC.

Refer to section 07840 of the specifications. For Quality Control requirements, refer to the Quality Control portion of the specification. 2. Details shown are typical details. If field conditions do not match requirements of typical

details, approved alternate details shall be utilized. Field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following:

Minimum and maximum Width of Joints

Type and thickness of fire-rated construction. The minimum assembly rating of the firestop assembly shall meet or exceed the highest rating of the adjacent construction.

If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable. Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments. References:

2017 Underwriter's Laboratories Fire Resistance Directory, Volume 2

Intertek Directory of Building **Products** 

All governing local and regional building codes

Current as of November 19, 2017. System details subject to change without notice.

after reading and replace details could result in an and or the intended temperate as of February 2015. On the details, refer to the ce Directory (volume 2.)"

JOB NUMBER: DRAWN: CHECKED: ISSUE DATE: 01-25-2018

**REVISIONS:** 

SHEET NAME: Joints-Gypsum-Shaft-

**SHEET NUMBER** 

281F/		<b>-</b>	89
<b>AND</b>	System No. HW	T	System No. HW-D-0758  1. Floor Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concepts and so the constructed of any 6 in. (152 mm) thick UL Classified hollow-core Precast Concrete Units*.
Classified by	ANSI/UL2079	CAN/ULC S115	1. Floor Assembly — Min 4-1/2 in. (114 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural conc
Underwriters Laboratories, Inc. to UL 2079 and CAN/ULC-S115	Assembly Ratings — 1 and 2 Hr (See Item 2)	F Rating — 1 and 2 Hr (See Ite	See Precast Concrete Units category in the Fire Resistance Directory for names of manufactures.
	Nominal Joint Width — 1/2 or 3/4 In. (See Item 3)  Class II or III Movement Capabilities — 50%  Compression or Extension or 66% Compression Only	FT Rating — 1 and 2 Hr (See Ite  FH Rating — 1 and 2 Hr (See Ite	the manner described in the individual U400, V400 Series Wall and Partition Design in the UL Fire Resistance Directory and sha
	L Rating at Ambient — Less than 1 CFM/Lin Ft	FTH Rating — 1 and 2 Hr (See Ite	A. Steel Floor and Ceiling Runners — Floor and ceiling runners of wall assembly shall consist of min No. 25 gauge galv steel channels:
	L Rating at 400° F — Less than 1 CFM/Lin Ft	Nominal Joint Width - 13 or 19 mm (See Ite	to accommodate steel status (tell 2D). I large regint of celling furnier shall be first 174 in. (of first) years that may exercise upon the
	Entaining at 400 T — Less train For William	Class II or III Movement Capabilities —	A1. Light Gauge Framing* — Slotted Ceiling Runner — As an alternate to the ceiling runner in Item 2A, slotted ceiling runner to consist
		Compression or Extension or 66% Compression	
		L Rating at Ambient — Less than 1.55 L/s/	Win m BRADY CONSTRUCTION INNOVATIONS INC, DBA SLIPTRACK SYSTEMS — SLP-TRK
		L Rating at 400° F — Less than 1.55 L/s/	CALIFORNIA EXPANDED METAL PRODUCTS CO — CST  CLARKDIETRICH BUILDING SYSTEMS — Types SLT, SLT-H
			MARINO/WARE, DIV OF WARE INDUSTRIES INC — Type SLT
			METAL-LITE INC — The System SCAFCO STEEL STUD MANUFACTURING CO — Slotted Track
			TELLING INDUSTRIES L L C — True-Action Deflection Track
	ı	1	A2. Light Gauge Framing* — Vertical deflection Ceiling Runner — As an alternate to the ceiling runners in Items 2A and 2A1, vertical deflection ceiling runner to consist of galv steel channel with slotted vertical deflection clips mechanically fastened within runner. Slott
	<del> </del>	<b>→</b>	clips, provided with step bushings, for permanent fastening of steel studs. Flanges sized to accommodate steel studs (Item 2B). Vertic
		<u> </u>	deflection ceiling runner secured to concrete floor slab with steel fasteners or steel masonry anchors spaced max 24 in. (610 mm) OC THE STEEL NETWORK INC — VertiTrack VTD250, VTD362, VTD400, VTD600 and VTD800
		<b>√</b> √	A3. Light Gauge Framing* — Notched Ceiling Runner — As an alternate to the ceiling runners in Items 2A through 2A3, notched ceiling
	. 4	. 4 4	runners to consist of C-shaped galv steel channel with notched return flanges sized to accommodate steel studs (Item 2B). Notched crunner secured to concrete floor slab with steel masonry anchors or steel fasteners spaced max 24 in. (610 mm) OC.
	' <del>                                     </del>		OLMAR SUPPLY INC — Type SCR
			B. Studs — Steel studs to be min 3-1/2 in. (89 mm) wide and formed of min 25 ga galv steel. Studs cut 3/4 to 1 in. (19 to 25 mm) less in length than assembly height with bottom nesting in and secured to floor runner. Steel studs nested in ceiling runner without attachmen
		3 (1)	Studs spaced max 24 in. (610 mm) OC.
			C. Gypsum Board* — Gypsum board 1/2 or 5/8 in. (13 or 16 mm) thick, applied on both sides of wall as specified in the individual Wall as
		U     (2A)	Partition Design except that a max 3/4 in. (19 mm) gap shall be maintained between the top of the gypsum board and the bottom of the floor assembly. The screws attaching the gypsum board to studs at the top of the wall shall be located 1 in. (25 mm) to 1-1/2 in. (38 mm).
	(2B)		below the bottom edge of the ceiling runner. No gypsum board attachment screws shall be driven into the ceiling runner.
			The hourly ratings of the joint system are equal to the hourly fire rating of the wall.  3. Fill, Void or Cavity Material* — Top Track Seal — When max separation between the bottom of floor and top of wall is 1/2 in. (13 mm), the
	·		system is designed to accommodate a max 50 percent compression or extension from its installed width. When max separation between
			bottom of floor and top of wall is 3/4 in. (19 mm), the joint system is designed to accommodate a max 66% compression only from its insta width. Factory supplied foam seal installed over the ceiling runners (Item 2A) prior to attachment to underside of concrete floor in accorda
			with the installation instructions.
			HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CFS-TTS 358, CFS-TTS 600 or CFS-TTS-OS
			* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada respectively.
	Reproduced by HILTI, Inc	Courtesy of	Reproduced by HILTI, Inc. Courtesy of
	Underwriters Laborato  December 21, 20		Underwriters Laboratories, Inc.  December 21, 2015
Hilti Firesto	p Systems	, iii	Page: 1 of 2 Hilti Firestop Systems

Notes: Refer to section 07840 of the specifications. For Quality Control requirements, refer to the Quality Control portion of the specification. 2. Details shown are typical details. If field conditions do not match requirements of typical details, approved alternate details shall be utilized. Field

conditions and dimensions need

ation)> t meeting the

to be verified for compliance

with the details, including but

not limited to the following: Minimum and maximum Width of Joints

Type and thickness of fire-rated construction. The minimum assembly rating of the firestop assembly shall meet or exceed the highest rating of the adjacent construction.

If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable. Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

References:

2017 Underwriter's Laboratories Fire Resistance Directory, Volume 2

Intertek Directory of Building **Products** 

All governing local and regional building codes

Current as of November 19, 2017. System details subject to change without notice.

> JOB NUMBER: DRAWN: CHECKED: ISSUE DATE: 01-25-2018

SHEET NUMBER

**REVISIONS:** 

SHEET NAME:

Residential - Flat Deck **Gypsum-Chase-Walls** 

Wall may also be constructed of any UL Classified Concrete Blocks\*.

See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.

3. Joint System — Max separation between bottom of floor assembly and top of concrete wall at time of installation is 1 in. (25 mm). The joint system is designed to accommodate a max 12.5 percent compression or extension from its installed width. The joint system shall consists of the following:


A. Fill, Void or Cavity Material\* - Sealant — A 1/2 in. (13 mm) thickness of fill material installed within the joint, flush with each surface of the wall.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP606 Flexible Firestop Sealant

B. Forming Material — (Optional, Not Shown) - Mineral wool insulation or polyurethane foam backer rod. Forming material to be recessed from both surfaces of the wall as required to accommodate the required thickness of fill material.

Hilti Firestop Systems

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. June 26, 2008



Floor Assembly — Min 6 in. (152 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete.
 Wall Assembly — Min 6 in. (152 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m3) structural concrete.
 Wall Assembly — Min 6 in. (152 mm) thick reinforced Blocks\*.
 See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
 Joint System — Max separation between bottom of floor and top of wall (at time of installation of joint system) is 2 in. (51 mm). The joint system is designed to accommodate a max 6 percent compression or extension from its installed width. The joint system shall consist of the following:

 A. Forming Material — Min 4 pcf (64 kg/m3) mineral wool batt insulation installed in joint opening as a permanent form. Pieces of batt cut to min width of 5 in. (127 mm) and installed edge-first into joint opening, parallel with joint direction, such that batt sections are compressed min 50 percent in thickness and such that the compressed batt sections are recessed from both surfaces of the wall as required to accommodate the required thickness of fill material. Adjoining lengths of batt to be tightly-butted with butted seams spaced min 24 in. (610 mm) apart along the length of the joint.
 B. Fill, Void or Cavity Material\* — Sealant — Min 1/2 in. (13 mm) thickness of fill material applied within the joint, flush with both surfaces of the wall.

wall.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP606 Flexible Firestop Sealant

Hilti Firestop Systems

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. September 09, 2005

Page: 1 of 1

Motos:

- Refer to section 07840 of the specifications. For Quality Control requirements, refer to the Quality Control portion of the specification.
  - Details shown are typical details. If field conditions do not match requirements of typical details, approved alternate details shall be utilized. Field conditions and dimensions need to be verified for compliance with the details, including but not limited to the following:
  - Minimum and maximum Width of Joints
- \* Type and thickness of fire-rated construction. The minimum assembly rating of the firestop assembly shall meet or exceed the highest rating of the adjacent construction.
- 3. If alternate details matching the field conditions are not available, manufacturer's engineering judgment drawings are acceptable. Drawings shall follow the International Firestop Council (IFC) Guidelines for Evaluating Firestop Systems Engineering Judgments.

  4. References:
- \* 2017 Underwriter's
  Laboratories Fire Resistance
  Directory, Volume 2
- Intertek Directory of Building
  Products
- All governing local and regional building codes

Current as of November 19, 2017. System details subject to change without notice. Any modification to these details could result in an applicatic
 UL or Intertek Classification or the intended temperature or t
 Details shown are up to date as of February 2015.
 For additional information on the details, refer to the most contact.

4.9

Residential - Flat Deck Joints-Concrete or

JOB NUMBER:

DRAWN:

CHECKED:

**REVISIONS:** 

SHEET NAME:

**Masonry Walls** 

**SHEET NUMBER** 

ISSUE DATE: 01-25-2018